PU voltages for 34kV service to Guardian Pipeline Gas Compression Facility

Existing 34 KV System		
	Voltage at TSS83	Voltage at Motor
Motor Running	1.05	0.84
Motor Starting	0.81	0.65

New 138-34 KV Substation		
	Voltage at New Station	Voltage at Motor
Motor Running	1.06	1.03
Motor Starting	0.92	0.81