

**TABLE III**

**2021 Summer Peak Double Contingencies without MVP-16  
Overloads on MidAmerican Facilities >100 kV**

<b>Overloaded Line</b>	<b>Line Loading (MVA)</b>	<b>Line Loading (%)</b>	<b>Outaged Lines</b>
Neal North - Salix 161 kV*	278	124	Raun-Neal North 161 kV #1 & Raun-Neal North 161 kV #2
Neal North - Raun 161 kV #2*	372	111	Neal North-Salix 161 kV & Raun-Neal North 161 kV #1
Neal North - Raun 161 kV #1*	372	111	Neal North-Salix 161 kV & Raun-Neal North #2 161 kV

\*Mitigation plans are in place for these facilities