

**MidAmerican Exhibit 11.2N  
 2021 Summer Peak Load  
 Double Contingency Overloads With or Without MVP-16  
 Clean Line In-Service  
 Gateway Project In-Service  
 MidAmerican Facilities > 100 kV**

Overloaded Line	Line Loading (MVA)	Line Loading (%)	Outaged Lines/Transformers
Neal North-Salix 161 kV*	281	124	Raun-Neal 161 kV #1 & Raun-Neal North 161 kV #2
Raun-Neal North 161 kV #2*	382	111	Neal North-Salix 161 kV #1 & Raun-Neal North 161 kV #1
Raun-Neal North 161 kV #1*	382	111	Neal North-Salix 161 kV & Raun-Neal North 161 kV #2

\*Mitigation plans are in place for these facilities