

MidAmerican Exhibit 11.3N
2021 Summer Peak Load
Double Contingency Overloads With or Without MVP-16
Clean Line In-Service
Gateway Project Not In-Service
MidAmerican Facilities > 100 kV

Overloaded Line	Line Loading (MVA)	Line Loading (%)	Outaged Lines/Transformers
Neal North-Salix 161 kV*	281	124	Raun-Neal 161 kV #1 & Raun-Neal North 161 kV #2
Raun-Neal North 161 kV #2*	382	111	Neal North-Salix 161 kV #1 & Raun-Neal North 161 kV #1
Raun-Neal North 161 kV #1*	382	111	Neal North-Salix 161 kV & Raun-Neal N. 161 kV #2

*Mitigation plans are in place for these facilities