

Small Business Energy Efficiency Program GPY3 Evaluation Report

Final

Energy Efficiency Plan: Gas Plan Year 3 (6/1/2013-5/31/2014)

Presented to Nicor Gas Company

July 17, 2015

Prepared by:

Charles Ampong Navigant Consulting, Inc. Paul Higgins Navigant Consulting, Inc.

www.navigant.com



Submitted to:

Nicor Gas Company 1844 Ferry Road Naperville, IL 60563

Submitted by:

Navigant Consulting, Inc. 30 S. Wacker Drive, Suite 3100 Chicago, IL 60606 Phone 312.583.5700 Fax 312.583.5701

Contact:

Randy Gunn, Managing Director 312.938.4242 randy.gunn@navigant.com

Charley Budd, Director 312.583.4135 charley.budd@navigant.com

Disclaimer: This report was prepared by Navigant Consulting, Inc. ("Navigant") for Nicor Gas based upon information provided by Nicor Gas and from other sources. Use of this report by any other party for whatever purpose should not, and does not, absolve such party from using due diligence in verifying the report's contents. Neither Navigant nor any of its subsidiaries or affiliates assumes any liability or duty of care to such parties, and hereby disclaims any such liability.



Table of Contents

| E. | Exe | ecutive Summary | 1 |
|----|------|--|----------|
| | E.1. | Program Savings | |
| | E.2. | Program Savings by Measure Type | 2 |
| | E.3. | Impact Estimate Parameters | |
| | E.4. | Program Volumetric Details | 3 |
| | E.5. | Findings and Recommendations | 4 |
| 1. | Intr | roduction | 6 |
| | 1.1 | Program Description | 6 |
| | 1.2 | Evaluation Objectives | <i>6</i> |
| 2. | Eva | ıluation Approach | 7 |
| | 2.1 | Primary Data Collection | |
| | | 2.1.1 Overview of Data Collection Activities | 7 |
| | | 2.1.2 Verified Savings Parameters | |
| | | 2.1.3 Verified Gross Program Savings Analysis Approach | |
| | | 2.1.4 Verified Net Program Savings Analysis Approach | g |
| | | 2.1.5 Process Evaluation | g |
| 3. | Gro | oss Impact Evaluation | 10 |
| | 3.1 | Tracking System Review | 10 |
| | 3.2 | Program Volumetric Findings | 11 |
| | 3.3 | Gross Program Impact Parameter Estimates | 13 |
| | 3.4 | Development of the Gross Realization Rate | 15 |
| | 3.5 | Verified Gross Program Impact Results | 16 |
| 4. | Net | t Impact Evaluation | 17 |
| 5. | Pro | cess Evaluation | 19 |
| 6. | Fine | dings and Recommendations | 20 |
| 7. | | pendix | |
| | 7.1 | Detailed Impact Research Findings and Approaches | |
| | | 7.1.1 Gross Impact Savings Errata Correction | 22 |



List of Figures and Tables

| Figures | |
|--|----|
| Figure E-1. Year-over-Year Differences in SBEEP Participation and Saving Savings | 4 |
| Figure 3-1. Relative Importance of DI vs. CI Measures | |
| Figure 4-1. SBEEP Yearly Comparison Actual vs. Planned Savings | 18 |
| Tables | |
| Table E-1. Total GPY3 SBEEP Natural Gas Savings | 2 |
| Table E-2. Nicor Gas GPY3 SBEEP Results by Measure Type | |
| Table E-3. Verified Gross and Net Savings Parameter Data Sources | 3 |
| Table E-4. GPY3 SBEEP Primary Participation Detail | 3 |
| Table 2-1. GPY3 SBEEP Core Evaluation Activities | 7 |
| Table 2-2. Verified Gross and Net Savings Parameter Data Sources | 8 |
| Table 3-1. GPY3 SBEEP Volumetric Findings | |
| Table 3-2. GPY3 SBEEP Installed Measures by Type | |
| Table 3-3. Verified Gross Savings Parameters | |
| Table 3-4. GPY3 SBEEP Gross Realization Rate by Measure | |
| Table 3-5. GPY3 SBEEP Verified Gross Impact Savings Estimates | |
| Table 4-1. GPY3 SBEEP Verified Net Savings Estimates by End-use Category | |
| Table 7-1. Illinois TRM - Faucet Aerator Water Usage Table | |



E. Executive Summary

This report presents a summary of the findings and results of the impact and process evaluation of the Nicor Gas Small Business Energy Efficiency Program (SBEEP) in its third year of operation, which is program year 3 (GPY3). SBEEP is designed to assist qualified Nicor Gas non-residential customers to achieve gas energy savings by educating them about energy efficiency (EE) opportunities through on-site assessments conducted by trade allies and installation of no-cost direct-install (DI) natural gas energy efficiency measures. Further savings are available to participating customers through incentives offered for select contractor-installed (CI) natural gas efficient measures.

Key changes during GPY3 included the separation of Nicor Gas's SBEEP from the previously joint implementation of the Small Business Energy Savings Program with ComEd, Peoples Gas and North Shore Gas after GPY2. Also, Nexant Inc. (Nexant) continued as the implementation contractor (IC) for SBEEP in GPY3, but implementation was transitioned to CLEAResult for the next program year. The change in implementation contractor is important to note, since acting on some of the recommendations in this report will involve CLEAResult. Nicor introduced several new measures for SBEEP in GPY3, included steam heating/process pipe insulation measures. The majority of the savings from SBEEP measures installed in GPY3 were derived from deemed values contained in the Illinois Technical Reference Manual (TRM).³

As agreed to in the GPY3 plan, the scope of the GPY3 evaluation effort was limited. Navigant's evaluation, measurement and verification (EM&V) of SBEEP GPY3 impacts consisted of verifying compliance with the methods and values specified in the TRM, or, in cases of custom (i.e., non-deemed) measures, evaluating and, where appropriate, adjusting savings. The net-to-gross (NTG) value used to calculate GPY3 net savings was deemed by the Illinois Energy Efficiency Stakeholder Advisory Group (SAG).⁴ Process research of GPY3 SBEEP evaluation consisted of interviews with program and IC staff to verify information about Program performance, measures, and tracking systems.

E.1. Program Savings

Table E-1 summarizes the natural gas savings from SBEEP in GPY3. Navigant verified net savings of 2,780,216 therms.

¹ The GPY3 program year began June 1, 2013 and ended May 31, 2014.

² To qualify for SBEEP, customers must be active Commercial and Industrial (C&I) customers of Nicor Gas who use up to 60,000 therms per year.

³ State of Illinois Energy Efficiency Technical Reference Manual_Effective_060113_Version_2.0_060713_Clean.pdf

⁴ See http://www.ilsag.info/ for more information on the SAG and the net-to-gross framework.



Table E-1. Total GPY3 SBEEP Natural Gas Savings

| Savings Category | Energy Savings (Therms) |
|---------------------------------|-------------------------|
| Ex-Ante Gross Savings (Therms) | 2,855,341 |
| Ex-Ante Net Savings (Therms) | 2,855,341 |
| Verified Gross Savings (Therms) | 2,780,216 |
| Gross Realization Rate | 97%‡ |
| Net to gross ratio (NTG) | 1.00† |
| Verified Net Savings (Therms) | 2,780,216 |

Source: Utility tracking data and Navigant analysis; ‡ Based on evaluation research findings † Deemed value, Source: http://ilsagfiles.org/SAG_files/Meeting_Materials/2013/August 5-6, 2013
Meeting/Nicor_Gas_NTG_Results and Application PY1-3.pdf.

E.2. Program Savings by Measure Type

Table E-2 summarizes the program savings by measure type.

Table E-2. Nicor Gas GPY3 SBEEP Results by Measure Type

| Rebate Measure Kind | Ex-Ante Gross Savings (therms) | Gross Realization Rate‡ | Verified Gross Savings (therms) | NTGt | Verified Net Savings (therms) |
|--------------------------------|--------------------------------|-------------------------------|---------------------------------------|------|-------------------------------------|
| Bathroom Aerators (DI & CI) | 30,480 | 112% | 34,015 | 1.00 | 34,015 |
| Kitchen Aerators (DI & CI) | 1,141 | 154% | 1,762 | 1.00 | 1,762 |
| Showerheads | 358,325 | 79% | 281,893 | 1.00 | 281,893 |
| Pre-Rinse Sprayers | 2,139 | 100% | 2,139 | 1.00 | 2,139 |
| Boiler Reset Control | 4,343 | 80% | 3,474 | 1.00 | 3,474 |
| Boiler Tune-up | 5,458 | 80% | 4,367 | 1.00 | 4,367 |
| Efficient Furnace | 21,057 | 96% | 20,166 | 1.00 | 20,166 |
| Furnace Tune-up | 13,797 | 100% | 13,797 | 1.00 | 13,797 |
| Water Heater (+88% TE) | 251 | 100% | 251 | 1.00 | 251 |
| HW Pipe Wrap/Insulation | 32,122 | 100% | 32,122 | 1.00 | 32,122 |
| Programmable Thermostat | 675,866 | 100% | 675,866 | 1.00 | 675,866 |
| Salon sprayer | 800 | 100% | 800 | 1.00 | 800 |
| Steam Traps | 1,709,564 | 100% | 1,709,564 | 1.00 | 1,709,564 |
| Program Total | 2,855,341 | 97% | 2,780,216 | 1.00 | 2,780,216 |

Source: Utility tracking data and Navigant analysis; ‡ Evaluation research

[†] A deemed value approved by the Illinois Energy Efficiency Stakeholder Advisory Group (SAG).



E.3. Impact Estimate Parameters

In the course of estimating verified gross and net savings, the evaluation team used a variety of parameters in its calculations. Most of the measure savings parameters were deemed for this program year and others were adjusted based on evaluation research. The key parameters used in the analysis are shown in Table E-3.

Table E-3. Verified Gross and Net Savings Parameter Data Sources

| Parameter | Data Source | Deemed or Evaluated? |
|-----------------------------|---------------------------|----------------------|
| Net-to-Gross Ratio (NTGR) | SAG Spreadsheet † | Deemed |
| Deemed per-unit savings | IL-TRM (v2.0) and (v3.0)‡ | Deemed |
| Non-deemed per-unit savings | Evaluation Research | Evaluated |
| Gross Realization Rate | Program tracking data | Evaluated |

[†] Deemed values. Source: http://ilsagfiles.org/SAG_files/Meeting_Materials/2013/August 5-6, 2013

Meeting/Nicor Gas NTG Results and Application PY1-3.pdf.

Illinois_Statewide_TRM_Effective_060113_Version_2.0_060713_Clean.pdf

Illinois_Statewide_TRM_Effective_060114_Version_3 0_021414_Final_Clean.pdf (for HVAC/aerator errata corrections).

E.4. Program Volumetric Details

As shown in Table E-4, SBEEP implemented 1,974 unique projects and 30,789 measures in GPY3.

Table E-4. GPY3 SBEEP Primary Participation Detail

| Participation | Direct-Install | Contractor-Installed | Total |
|-----------------------------|----------------|----------------------|---------|
| Total Implemented Projects | 321 | 1,819 | 1,974* |
| Total Participant Customers | 267 | 1,522 | 1,628** |
| Total Program Measures | 15,749 | 15,040 | 30,789 |

Source: Utility tracking data and Navigant analysis.

Figure E-1 compares the SBEEP savings in GPY3 with the savings in GPY1 and GPY2, as well as year-over-year differences in program participation and verified net savings. Participation and savings have both grown substantially since GPY1, the first full year of the Program's operation.

[‡] Source: State of Illinois Technical Reference Manuals:

^{*} Unique projects: excludes 166 duplicate projects which had both CI and DI measures installed.

^{**} Unique customers: excludes 161 duplicate customer names with both CI and DI measures installed.






Figure E-1. Year-over-Year Differences in SBEEP Participation and Saving Savings

Source: Nicor Gas tracking data and Navigant analysis.

E.5. Findings and Recommendations

The following provides insights into key program findings and recommendations.

Gross Realization Rate

Finding 1. The GPY3 gross realization rate was 97 percent.⁵ The evaluation team corrected TRM errata measures by adjusting the ex-ante per-unit savings values from the tracking system for the space heating and water efficiency measures. The adjustments were to ensure compliance with the SAG and the Illinois TRM Technical Advisory Committee directive to apply corrections to TRM (v2.0) errata measures using the TRM (v3.0) effective June 1, 2013. ⁶ The adjustments slightly reduced the claimed savings for the space heating measures and increased the savings for the water efficiency aerators. The evaluation team adjusted the unit savings value for showerheads downward based on the number of showers per day assumptions reported in the tracking system. Overall, the errata savings adjustments reduced the verified net savings by 75,125 therms, or 3 percent.

⁵ Gross Realization Rate = verified gross savings / tracking ex-ante gross savings

⁶ Directive from the Illinois TRM Technical Advisory Committee and the SAG indicated that when a measure error was identified (in V2 TRM) and the TAC process resulted in a consensus, the measure is identified (in V3 TRM) as an 'Errata'. In these instances the measure code indicates that a new version of the measure has been published, and that the effective date of the measure dates back to June 1st, 2013" (refer to pages 10-15 of V3 TRM).



Recommendation 1. The new GPY4 implementation contractor, CLEAResult, should review SBEEP unit measure savings values with any new updates to the TRM for GPY4 and GPY5 program years.

Savings Verification Process

Finding 2. The SBEEP tracking database contains input fields to hold most of the program measure savings assumptions, but not all of these assumptions are tracked. The evaluation team required verification of the input capacities for the condensing furnaces, boiler input capacities for the boiler tune-ups and reset control measures, and baseline and existing efficiencies for the condensing furnace measures. As noted above, Navigant adjusted the savings for these measures using the TRM (v3.0).

Recommendation 2a. To reduce the potential for evaluation savings adjustment, CLEAResult should consider producing a spreadsheet that documents the methodology, assumptions, and algorithms for establishing the unit savings values for each SBEEP measure and making that accessible to the evaluation team for review and feedback prior tracking system implementation.

Recommendation 2b. Nicor Gas and CLEAResult, together with Navigant, should explore the opportunity of granting approval for the evaluation team to gain direct real-time, read-only access to the SBEEP tracking system to review project-specific documents, quantities, and invoices for measure and savings verification. Similar arrangement exists for the Nicor Gas Business Custom Incentive Program, which has improved the efficiency of the evaluation process for implementer and evaluator.

Program Savings Goals Attainment

Finding 3. The GPY3 SBEEP achieved verified net savings of 2,780,216 therms, which is 188 percent greater than the filed GPY3 net savings goal of 965,294 therms.⁷ The GPY3 verified net savings showed an increase of 30 percent from GPY2. The increase in savings was primarily due to continued customer participation in steam trap replacements in the dry cleaning market during GPY2 and GPY3. (This single measure accounted for 84 percent of program net savings in GPY2 and 61 percent of net savings in GPY3.)

Program Participation

Finding 4. The SBEEP's biggest participation successes have been the result of matching a well-defined niche market with a motivated trade group and a widely-shared need for a particular measure (e.g. steam traps to Korean dry cleaners, showerheads to hotels/motels).

Recommendation 4. Nicor Gas should consider conducting a market assessment to identify more niche matches, to expand upon the success of dry cleaner steam traps and hotel/motel showerheads.

⁷ Nicor Rider 30 4rd Quarterly Report GPY3 ICC Filing, Order Docket 10-0562.



1. Introduction

1.1 Program Description

SBEEP is designed to assist qualified Nicor Gas non-residential customers⁸ to achieve gas energy savings by educating them about energy efficiency (EE) opportunities through on-site assessments conducted by trade allies and installation of no-cost direct-install (DI) natural gas energy efficiency measures. Further savings are available to participating customers through incentives of 30 to 75 percent offered for select contractor-installed (CI) natural gas efficient measures.

New measures introduced in GPY3 SBEEP include steam heating/process pipe insulation measures. The majority of the savings from the measures installed in GPY3 are derived from deemed values contained in the Illinois Technical Reference Manual (TRM). The GPY3 evaluation involved verifying the compliance of SBEEP with the TRM, or in the case of custom measures, applying research-based adjustments where necessary to non-deemed savings. The net-to-gross (NTG) value used to calculate GPY3 net savings was deemed by the Illinois Energy Efficiency Stakeholder Advisory Group (SAG). Process research related to the GPY3 evaluation was conducted through interviews with program staff and implementation contractor staff to verify information about program performance, measures, and the tracking system.

1.2 Evaluation Objectives

The planned scope of the GPY3 evaluation effort was limited. The objectives of GPY3 evaluation are to:

- (1) Provide an independent calculation of the net therm savings produced by the program in GPY3
- (2) Review the assumptions and calculations of savings in the tracking data in compliance with the statewide TRM, and determine what changes are required
- (3) Interview program staff and the implementation contractor to receive an update on program marketing, delivery, goals and challenges to gain context for the GPY3 evaluation, and identify issues to consider in GPY4 planning.

⁸ To qualify for SBEEP, customers must be active Commercial and Industrial (C&I) customers of Nicor Gas who use up to 60,000 therms per year.

⁹ State of Illinois Energy Efficiency Technical Reference Manual_Effective_060113_Version_2.0_060713_Clean.pdf ¹⁰ See http://www.ilsag.info/ for more information on the SAG and net-to-gross framework.



2. Evaluation Approach

This evaluation of the GPY3 SBEEP reflects the third full-scale year of Rider 30 Nicor Gas Energy Efficiency Portfolio. This section describes the data that Navigant collected and the method for analyzing the data to meet the GPY3 evaluation objectives.

2.1 Primary Data Collection

2.1.1 Overview of Data Collection Activities

The core data collection activities for the GPY3 evaluation are shown in Table 2-1.

| Program | Process Evaluation | NTG Research | Tracking Data Review | Project File Reviews | On- site M&V | Billing Analysis | Other |
|--|-----------------------|-----------------|----------------------------|----------------------------|--------------------|---------------------|-------------------|
| Small Business Energy Efficiency Program | PM/IC Interviews | None | Yes | No | No | No | TRM Compliance |

Table 2-1. GPY3 SBEEP Core Evaluation Activities

The core activity in the GPY3 evaluation was tracking system review of measure type and savings using the tracking data received from the implementation contractor on October 2, 2014. This involved early review of the input fields of the tracking system for the program, and providing feedback to the implementation contractor of what additional inputs were necessary to track for the evaluation exercise. Additional interviews were conducted with program staff and implementation contractor staff to assess program performance, and for clarification on tracking system inputs.

As Table 2-1 indicates, the evaluation in GPY3 focused on impact evaluation through a tracking system data review, with a limited process evaluation component. As a result, the impact and process findings and recommendations are brief.

2.1.2 Verified Savings Parameters

Navigant estimated verified per-unit savings for each program measure using impact algorithm sources found in the Illinois TRM for deemed measures, and evaluation research for non-deemed measures. Table 2-2 below presents the sources for parameters that were used in verified gross savings analysis indicating which were examined through GPY3 evaluation research and which were deemed.



Table 2-2. Verified Gross and Net Savings Parameter Data Sources

| Parameter | Data Source | Deemed or Evaluated? |
|--|--|----------------------|
| Measure Quantity Installed | Program tracking system | Evaluated |
| Net-to-Gross Ratio (NTGR) | SAG Spreadsheet † | Deemed |
| Gross Realization Rate | Program tracking data, TRM | Evaluated |
| Boiler Cutout/Reset Control | Illinois TRM, version 2.0, section 4.4.4‡ Used TRM (v3.0) for errata correction | Deemed |
| Space Heating Boiler Tune-Up | Illinois TRM, version 2.0, section 4.4.2‡ Used TRM (v3.0) for errata correction | Deemed |
| High Efficiency Furnaces | Illinois TRM, version 2.0, section 4.4.11‡ Used TRM (v3.0) for errata correction | Deemed |
| Pre-Rinse Sprayer | Illinois TRM, version 2.0, section 4.2.11‡ | Deemed |
| Water Heaters Savings Assumptions | Illinois TRM, version 2.0, section 4.3‡ | Deemed |
| Steam Traps Savings Assumptions | Illinois TRM, version 2.0, section 4.4.16‡ | Deemed |
| Kitchen & Bathroom Faucet Aerator | Illinois TRM, version 2.0, section 4.3.2‡ Used TRM (v3.0) for errata correction | Deemed |
| Showerhead | Illinois TRM, version 2.0, section 4.3.3‡ Used TRM (v3.0) for errata correction | Deemed |
| Steam Pipe Insulation Savings | Illinois TRM, version 2.0, section 4.4.14‡ | Deemed |
| HW Heater Insulation Jacket; Minimum R-8 | Illinois TRM, version 2.0, section 4.4.14‡ | Deemed |
| Furnace Tune-Up Savings | Evaluation Research (used GPY2 value) | Evaluated |
| Programmable Thermostat Savings | Evaluation Research (used GPY2 value) | Evaluated |

Source: Navigant analysis of program tracking data

† Deemed values. Source: http://ilsagfiles.org/SAG_files/Meeting_Materials/2013/August 5-6, 2013

Meeting/Nicor Gas NTG Results and Application PY1-3.pdf.

‡ Source: State of Illinois Technical Reference Manuals:

Illinois_Statewide_TRM_Effective_060113_Version_2.0_060713_Clean.pdf

Illinois_Statewide_TRM_Effective_060114_Version_3 0_021414_Final_Clean.pdf (for HVAC/aerator errata corrections).

2.1.3 Verified Gross Program Savings Analysis Approach

Methods for gross savings verification of TRM measures employed in GPY3 are tracking data review and engineering review of measure savings for compliance with the Illinois TRM. Version 2.0 was used for GPY3 evaluation except for measures with errata corrections where the Version 3.0 was used. For GPY3 non-deemed commercial and industrial measures, such as furnace tune-up and



programmable thermostats, Navigant relied on secondary research or previous years' non-deemed values to verify the claimed savings. The verified gross savings are the product of verified per-unit savings and verified measure quantities.

2.1.4 Verified Net Program Savings Analysis Approach

In GPY3 the NTG ratio estimate used to calculate the net verified savings was deemed by the SAG. For SBEEP, the deemed NTG ratio estimate was 1.00.

2.1.4.1 Free-Ridership

Since the NTG ratio was deemed for GPY3 and GPY4, no participant customer or trade ally free ridership was conducted as task of the GPY3 evaluation.

2.1.5 Process Evaluation

Navigant did not conduct participant customer surveys for GPY3 for process evaluation. The GPY3 process evaluation activities included interviews with program staff and implementation staff to assess program performance, the effectiveness of program implementation, and the tracking system.



3. Gross Impact Evaluation

The gross impact analysis involved tracking system review, verification of installed measures and measure savings. The verified savings were calculated by multiplying the quantity of measures installed by the verified measure unit savings. The program Gross Realization Rate was determined by the ratio of the verified savings and the tracking ex-ante savings. Navigant estimated that the SBEEP GPY3 Program achieved verified gross savings of 2,780,216 therms based on 97 percent gross realization rate.

3.1 Tracking System Review

Over the course of the GPY3 program year, Navigant and the program implementation contractor, Nexant, maintained close contact regarding the programs tracking system (PMT Data Management platform) updates and follow-up from previous program evaluation recommendations. Navigant provided early review and feedback on the additional input fields to the PMT tracking system for the GPY3 evaluation. Navigant used the data extracts from the program's tracking system received on October 2, 2014 to verify the GPY3 program ex-ante inputs including measure counts and ex-ante savings. Listed below are the key findings from the tracking system review.

- 1. The evaluation team used the TRM (v3.0) to correct errata and adjust the tracking gross savings for the space heating high efficiency condensing furnace, boiler tune-up and boiler reset control measures. The adjustments were in compliance with the SAG and the Illinois TRM Technical Advisory Committee's directive to apply corrections to errata measures in TRM (v2.0) using the TRM (v3.0) effective June 1, 2013.¹¹ The errata correction involved changing the measures savings formula from using input capacity for calculating savings by removing efficiency variable as described in Appendix 7.1.1. As an example, boiler reset control project SBEEP_169407 with 210 input capacity and 254 therms gross savings was changed to 203 therms verified savings (similarly, project SBEEP_169662 had 180 input capacity with 210 gross therms changed to 168 therms verified savings). For condensing furnaces, we referred to the measure description and defined AFUE and applied engineering judgment to determine the errata correction factor to adjust the claimed savings. The Gross Realization Rate for space heating measures with errata correction was 91 percent.
- 2. The evaluation team used the TRM (v3.0) algorithm and assumptions to correct errata and adjust the tracking savings for the bathroom and kitchen faucet aerators. The adjustment involved changing the average flow rate of the baseline faucet from 1.2 to 1.39 gallons per minute. The verified measure unit savings were calculated based on the reported business facility annual gallons mixed water per faucet assumptions in the TRM. The Gross Realization Rate for bath aerators was 112 percent and 154 percent for kitchen aerators.

¹¹ Directive from the Illinois TRM Technical Advisory Committee and the SAG indicated that when a measure error was identified (in V2 TRM) and the TAC process resulted in a consensus, the measure is identified (in V3 TRM) as an 'Errata'. In these instances the measure code indicates that a new version of the measure has been published, and that the effective date of the measure dates back to June 1st, 2013" (refer to pages 10-15 of V3 TRM).



- 3. The evaluation adjusted the per-unit savings from showerheads, where the number of showers per day assumptions reported in the tracking system did not produce the claimed savings. For instance, a showerhead with one shower per day should yield 21.63 therms savings annually, but several of the tracking savings are 43.4 or higher. The adjustment reduced the measure savings with 79 percent realization rate.
- 4. The tracking database has input fields to collect most of the program measure savings assumptions, but not all are tracked. The evaluation team required verification of the input capacities for the condensing furnaces, boiler input capacities for the boiler tune-ups and reset control measures, baseline and existing efficiencies of condensing furnaces. CLEAResult should consider developing a spreadsheet that documents the methodology, assumptions, and algorithms for setting per-unit savings values for each program measure.

3.2 Program Volumetric Findings

Table 3-2 disaggregates the program volumetric findings by program delivery channel. The GPY3 program implemented 1,974 unique projects and 30,789 measures from 1,628 participants.

Table 3-1. GPY3 SBEEP Volumetric Findings

| Participation | Direct-Install | Contractor-Installed | Total |
|-----------------------------|----------------|----------------------|---------|
| Total Implemented Projects | 321 | 1,819 | 1,974* |
| Total Participant Customers | 267 | 1,522 | 1,628** |
| Total Program Measures | 15,749 | 15,040 | 30,789 |

Source: Utility tracking data and Navigant analysis.

Figure 3-1 shows the distribution of measures and verified gross therms savings by program delivery channel since beginning of Rider 30 portfolio operations. The DI measures accounted for 51 percent of the total measure count compared to 49 percent for the CI measures. This is a significant jump from the 8 percent for DI measures in GPY2, due to increased installations of bathroom aerators and showerheads. Out of the 148 projects with showerheads, 138 projects came from Hotel/Motel/ Lodging customers. These customers installed 99 percent of the 8,226 showerheads installed through the program. The savings from DI measures also increased considerably to 11 percent, up from one percent in GPY2.

^{*} Unique projects: excludes 166 duplicate projects which had both CI and DI measures installed.

^{**} Unique customers: excludes 161 duplicate customer names with both CI and DI measures installed.






Figure 3-1. Relative Importance of DI vs. CI Measures

Source: Evaluation review of GPY3 SBEEP tracking database

Table 3-2 below provides measure disaggregation for the DI and the CI measures. The program continued to see participation from customers wanting commercial steam trap replacements for dry cleaners and programmable thermostats. New measures introduced in GPY3 included steam heating/process pipe insulation measures (6,001 linear feet of pipe insulation).



Table 3-2. GPY3 SBEEP Installed Measures by Type

| Program Delivery | Rebate Measure Kind | Units | Ex-Ante Measure Count | Verified Measure Count | Percent Count |
|----------------------|---|-------|-----------------------------|------------------------------|------------------|
| | Bathroom Aerators* | Each | 7,242 | 7,242 | 23.5% |
| Direct Install (DI) | Kitchen Aerators* | Each | 246 | 246 | 0.8% |
| Direct filstaff (DI) | Showerheads | Each | 8,226 | 8,226 | 26.7% |
| | Pre-Rinse Sprayers | Each | 35 | 35 | 0.1% |
| | Bathroom Aerators* | Each | 1,466 | 1,466 | 4.8% |
| | Kitchen Aerators* | Each | 80 | 80 | 0.3% |
| | Boiler Reset Control | Each | 14 | 14 | 0.0% |
| | Boiler Tune-up | Each | 33 | 33 | 0.1% |
| | Condensing Furnace Upgrade/Replacement | Each | 89 | 89 | 0.3% |
| | Furnace Tune-up | Each | 220 | 220 | 0.7% |
| Contractor Installed | Gas Water Heater up to 75 MBTUH +88% TE | Each | 1 | 1 | 0.0% |
| (CI) | HW Heater Insulation Jacket; Minimum R-8 | Each | 3 | 3 | 0.0% |
| | Steam Heating/Process Steam Pipe Insulation | Ln Ft | 6,001 | 6,001 | 19.5% |
| | Programmable Thermostat | Each | 3,799 | 3,799 | 12.3% |
| | Salon sprayer | Each | 8 | 8 | 0.0% |
| | Commercial Steam Traps Dry Cleaners) | Each | 3,326 | 3,326 | 10.8% |
| Program Total | Program Total | | 30,789 | 30,789 | 100% |

Source: Evaluation review of GPY3 SBEEP tracking database

3.3 Gross Program Impact Parameter Estimates

As described in Section 2, ex-ante energy savings were verified using the assumptions and algorithm as specified in the TRM (v2.0) or TRM (v3.0) for errata correction or through engineering analysis for non-deemed measures. Table 3-3 indicates the input parameters to estimate verified gross savings.

^{*} Overall 8,708 bathroom aerators and 326 kitchen aerators were installed directly by customers or through contractors and trade allies.



Table 3-3. Verified Gross Savings Parameters

| Measure/Input Parameters | Ex-Ante Value | Verified Value | Unit | Source |
|---|------------------|--|--------------|-----------------|
| Measure Quantity | 30,789 | 30,789 | | Evaluated |
| Gross Realization Rate | | 97% | | Evaluated |
| Commercial Steam Traps (Dry Cleaners) | 514 | 514 | therms/unit | Deemed TRM v2.0 |
| Programmable Thermostat | 178 | 178 | therms/unit | Evaluated |
| High Efficiency Condensing Furnace | V 2rv | | therms/unit | |
| Boiler Cutout/Reset Controls | Vary | in TRM v2.0 using TRM v3.0 algorithm | therms/MBTU | Deemed TRM v3.0 |
| Boiler Tune-up (Heating) | Vary | and assumptions | therms/MBTU | |
| Bathroom/Kitchen Aerator | 3.5 | Vary with building type | therms/unit | Deemed TRM v2.0 |
| Showerhead | Vary | Adjusted based on reported number of showers per day | therms/unit | Deemed TRM v2.0 |
| Furnace Tune-up | 63 | Acceptable as is | therms/unit | Evaluated |
| Pre Rinse Sprayers | 61 | 61 | therms/unit | Deemed TRM v2.0 |
| Salon Sprayer | 100 | 100 | therms/unit | Deemed TRM v2.0 |
| Gas Water Heater +88% TE | 251 | 251 | therms/unit | Deemed TRM v2.0 |
| HW Heater Insulation Jacket; Minimum R-8 | 16 | 16 | therms/unit | Deemed TRM v2.0 |
| Pipe Insulation | Vary | Acceptable as is | therms/Ln.ft | Deemed TRM v2.0 |

Source: Utility tracking data and Navigant analysis; Illinois TRM (version 2.0 & 3.0)



3.4 Development of the Gross Realization Rate

The program Gross Realization Rate was determined by calculating the ratio of the verified gross savings and the tracking ex-ante gross savings. Gross Realization Rates by measure type were calculated as shown in Table 3-4.

Table 3-4. GPY3 SBEEP Gross Realization Rate by Measure

| Rebate Measure Kind | Measure Count | Ex-Ante Gross Savings (therms) | Gross Realization Rate‡ | Verified Gross Savings (therms) |
|--|------------------|--------------------------------------|-------------------------------|---------------------------------------|
| Bathroom Aerators (DI & CI)) | 8,708 | 30,480 | 112% | 34,015 |
| Kitchen Aerators (DI & CI) | 326 | 1,141 | 154% | 1,762 |
| Showerheads | 8,226 | 358,325 | 79% | 281,893 |
| Pre-Rinse Sprayers | 35 | 2,139 | 100% | 2,139 |
| Boiler Reset Control | 14 | 4,343 | 80% | 3,474 |
| Boiler Tune-up | 33 | 5,458 | 80% | 4,367 |
| Condensing Furnace Upgrade/Replacement | 89 | 21,057 | 96% | 20,166 |
| Furnace Tune-up | 220 | 13,797 | 100% | 13,797 |
| Gas Water Heater up to 75 MBTUH +88% Thermal Eff. | 1 | 251 | 100% | 251 |
| HW Heater Insulation Jacket; Minimum R-8 | 3 | 48 | 100% | 48 |
| Pipe Insulation | 6,001 | 32,074 | 100% | 32,074 |
| Programmable Thermostat | 3,799 | 675,866 | 100% | 675,866 |
| Salon sprayer | 8 | 800 | 100% | 800 |
| Steam Trap Repair/Replacement | 3,326 | 1,709,564 | 100% | 1,709,564 |
| Program Total | 30,789 | 2,855,341 | 97% | 2,780,216 |

Source: Utility tracking data and Navigant analysis

As noted above, correcting the errata in the ex-ante savings estimate resulted in less savings for the space heating high efficiency condensing furnaces, boiler tune-up and, boiler reset control measures, but increased the savings for the bathroom and kitchen aerators. Adjustment to the showerhead exante savings resulted in considerably less savings, which affected the aggregated savings for the DI measures, with 81 percent gross realization rate as shown in Table 3-5 below. The overall program gross realization rate was 97 percent. Steam trap replacements in commercial dry cleaners dominated program savings, comprising roughly 61 percent of the verified savings in GPY3.¹²

[‡] Based on Evaluation research findings

¹² Steam traps in commercial dry cleaners have contributed 73 percent since introduction in PY2, or 65 percent of the overall program savings since Rider 30 commencement.



3.5 Verified Gross Program Impact Results

The verified gross impact results for the GPY3 SBEEP is 2,780,216 therms as shown in Table 3-5. The evaluation research was not based on a sampling strategy to verify measure gross savings since the TRM was mostly used to determine verified savings.

Table 3-5. GPY3 SBEEP Verified Gross Impact Savings Estimates

| Category | Sample | Energy Savings (therms) | 90/10 Significance? | |
|--------------------------|--------|----------------------------|---------------------|--|
| DI Measures | | | | |
| Ex-Ante Gross Savings | | 386,673 | | |
| Gross Realization Rate‡ | †NA | 0.81 | †NA | |
| Verified Gross Savings‡ | | 314,965 | | |
| Percent of Gross Savings | | 11% | | |
| CI Measures | | | | |
| Ex-Ante Gross Savings | | 2,468,669 | | |
| Gross Realization Rate‡ | †NA | 1.00 | †NA | |
| Verified Gross Savings‡ | | 2,465,251 | | |
| Percent of Gross Savings | | 89% | | |
| GPY3 SBEEP Total | | | | |
| Ex-Ante Gross Savings | | 2,855,341 | | |
| Gross Realization Rate‡ | †NA | 0.97 | †NA | |
| Verified Gross Savings‡ | | 2,780,216 | | |

Source: Utility tracking data and Navigant analysis

[‡] Based on Evaluation research findings

tNA when the TRM determines the gross savings.



4. Net Impact Evaluation

As noted in Section 2, the SAG¹³ approved a net-to-gross ratio of 1.00 to be used to calculate GPY3 verified net savings for SBEEP. The evaluation calculated verified net savings of 2,780,216 therms for the GPY3 program as shown in Table 4-1.

Table 4-1. GPY3 SBEEP Verified Net Savings Estimates by End-use Category

| Category | Sample | Energy Savings (therms) | 90/10 Significance? |
|---------------------------|--------|----------------------------|---------------------|
| DI Measures | | | |
| Ex-Ante Gross Savings | | 386,673 | |
| Gross Realization Rate‡ | †NA | 0.81 | †NA |
| Verified Gross Savings‡ | 1 | 314,965 | |
| Net-to-Gross (NTG) Ratio† | | 1.00 | |
| Verified Net Savings | | 314,965 | |
| CI Measures | | | |
| Ex-Ante Gross Savings | | 2,468,669 | |
| Gross Realization Rate‡ | †NA | 1.00 | †NA |
| Verified Gross Savings‡ | | 2,465,251 | |
| Net-to-Gross (NTG) Ratio† | | 1.00 | |
| Verified Net Savings | | 2,465,251 | |
| GPY3 SBEEP Total | | | |
| Ex-Ante Gross Savings | | 2,855,341 | |
| Gross Realization Rate‡ | | 0.97 | |
| Verified Gross Savings‡ | †NA | 2,780,216 | †NA |
| Net-to-Gross (NTG) Ratio† |] | 1.00 | |
| Verified Net Savings | | 2,780,216 | |

Source: Utility tracking data and Navigant analysis.

[‡] Based on evaluation research findings

tSAG approved NTG deemed value.

¹³ http://ilsagfiles.org/SAG files/Meeting Materials/2013/August 5-6, 2013 Meeting/Nicor Gas NTG Results and Application PY1-3.pdf.



Figure 4-1 below provides a comparison of SBEEP verified net savings and the planned savings filed to the Illinois Commerce Commission (ICC).¹⁴ With the exception of GPY1, which is the first full year of Rider 30 operation, SBEEP greatly exceeded planned energy savings targets year over year. The GPY3 Program exceeded goals by 188 percent. Overall the SBEEP three-year total verified net savings of 5,027,712 exceeded the portfolio planned net savings of 1,751,377 therms by 187 percent.




Figure 4-1. SBEEP Yearly Comparison Actual vs. Planned Savings

Source: Navigant analysis of GPY3 SBEEP tracking data GPY1 SBEEP Program Evaluation Report; GPY2 SBEEP Program Evaluation Report; Nicor Gas Energy Efficiency Plan 2011-2014 (Revised Plan Filed Pursuant to Order Docket No. 10-0562)

¹⁴ Nicor Gas Energy Efficiency Plan 2011-2014 (Revised Plan Filed Pursuant to Order Docket No. 10-0562)



5. Process Evaluation

The GPY3 process evaluation activities for SBEEP was limited to interviews with programs staff and the implementation contractor staff to verify information about marketing and outreach strategies made in GPY3 that impacted customer and trade ally participation and satisfaction. The impact evaluation in GPY3 consisted of tracking data engineering review; we did not conduct project-specific file reviews or on-site visits that can also be a source of process findings.

Information gathered through interviews and other communication did not raise concerns by the evaluation team that merited follow-up process research in GPY3. The observations will be considered when planning GPY4 evaluation activities.



6. Findings and Recommendations

This section summarizes the key findings and recommendations. Due to the limited scope of the GPY3 evaluation, this section is repeated in its entirety in the Executive Summary.

Gross Realization Rate

Finding 1. The GPY3 gross realization rate was 97 percent.¹⁵ The evaluation team corrected TRM errata measures by adjusting the ex-ante per-unit savings values from the tracking system for the space heating and water efficiency measures. The adjustments were to ensure compliance with the SAG and the Illinois TRM Technical Advisory Committee directive to apply corrections to TRM (v2.0) errata measures using the TRM (v3.0) effective June 1, 2013. ¹⁶ The adjustments slightly reduced the claimed savings for the space heating measures and increased the savings for the water efficiency aerators. The evaluation team adjusted the unit savings value for showerheads downward based on the number of showers per day assumptions reported in the tracking system. Overall, the errata savings adjustments reduced the verified net savings by 75,125 therms, or 3 percent.

Recommendation 1. The new GPY4 implementation contractor, CLEAResult, should review SBEEP unit measure savings values with any new updates to the TRM for GPY4 and GPY5 program years.

Savings Verification Process

Finding 2. The SBEEP tracking database contains input fields to hold most of the program measure savings assumptions, but not all of these assumptions are tracked. The evaluation team required verification of the input capacities for the condensing furnaces, boiler input capacities for the boiler tune-ups and reset control measures, and baseline and existing efficiencies for the condensing furnace measures. As noted above, Navigant adjusted the savings for these measures using the TRM (v3.0).

¹⁵ Gross Realization Rate = verified gross savings / tracking ex-ante gross savings

¹⁶ Directive from the Illinois TRM Technical Advisory Committee and the SAG indicated that when a measure error was identified (in V2 TRM) and the TAC process resulted in a consensus, the measure is identified (in V3 TRM) as an 'Errata'. In these instances the measure code indicates that a new version of the measure has been published, and that the effective date of the measure dates back to June 1st, 2013" (refer to pages 10-15 of V3 TRM).



Recommendation 2a. To reduce the potential for evaluation savings adjustment, CLEAResult should consider producing a spreadsheet that documents the methodology, assumptions, and algorithms for establishing the unit savings values for each SBEEP measure and making that accessible to the evaluation team for review and feedback prior tracking system implementation.

Recommendation 2b. Nicor Gas and CLEAResult, together with Navigant, should explore the opportunity of granting approval for the evaluation team to gain direct real-time, read-only access to the SBEEP tracking system to review project-specific documents, quantities, and invoices for measure and savings verification. Similar arrangement exists for the Nicor Gas Business Custom Incentive Program, which has improved the efficiency of the evaluation process for implementer and evaluator.

Program Savings Goals Attainment

Finding 3. The GPY3 SBEEP achieved verified net savings of 2,780,216 therms, which is 188 percent greater than the filed GPY3 net savings goal of 965,294 therms.¹⁷ The GPY3 verified net savings showed an increase of 30 percent from GPY2. The increase in savings was primarily due to continued customer participation in steam trap replacements in the dry cleaning market during GPY2 and GPY3. (This single measure accounted for 84 percent of program net savings in GPY2 and 61 percent of net savings in GPY3.)

Program Participation

Finding 4. The SBEEP's biggest participation successes have been the result of matching a well-defined niche market with a motivated trade group and a widely-shared need for a particular measure (e.g. steam traps to Korean dry cleaners, showerheads to hotels/motels).

Recommendation 4. Nicor Gas should consider conducting a market assessment to identify more niche matches, to expand upon the success of dry cleaner steam traps and hotel/motel showerheads.

-

¹⁷ Nicor Rider 30 4rd Quarterly Report GPY3 ICC Filing, Order Docket 10-0562.



7. Appendix

7.1 Detailed Impact Research Findings and Approaches

7.1.1 Gross Impact Savings Errata Correction

As noted in the above discussions, directive from the Illinois TRM Technical Advisory Committee and the SAG indicated that when a measure error was identified in TRM (v2.0)¹⁸ and the TAC process resulted in a consensus, the measure is identified in TRM (v3.0)¹⁹ as an 'Errata'. In these instances the measure code indicates that a new version of the measure has been published, and that the effective date of the measure dates back to June 1st, 2013" (refer to pages 10-15 of TRM v3.0). The errata correction involved changing the measures savings formula from using input capacity for calculating savings by removing efficiency variable. This changes results in reduction of the measure unit therms savings.

The GPY3 SBEEP measures affected by this directive are the high efficiency condensing furnaces, boiler tune-up for space heating, and boiler cutout/reset control measures. Others were bathroom and kitchen aerators. This section presents the TRM (v2.0) algorithm and the errata correction using the TRM (v3.0).

7.1.1.1 High Efficiency Furnace

TRM (v2.0) Algorithm and Assumption

Time of Sale:

ΔTherms = EFLH * Capacity * (1/AFUE(exist) - 1/AFUE(eff)) / 100,000 Btu/Therm

Early replacement

ΔTherms = EFLH * Capacity * (1/AFUE(base) - 1/AFUE(eff)) / 100,000 Btu/Therm

TRM (v3.0) Errata Correction

Time of Sale:

ΔTherms = EFLH * Capacity * ((AFUE(eff) – AFUE(base)/AFUE(base))/ 100,000 Btu/Therm

Early replacement

ΔTherms = EFLH * Capacity * (AFUE(eff) – AFUE(exist)/ AFUE(exist)) / 100,000 Btu/Therm

Where:

Capacity = Nominal Heating Capacity Furnace Size (btuh)

AFUE(exist) = Existing Furnace Annual Fuel Utilization Efficiency Rating

AFUE(base) = Baseline Furnace Annual Fuel Utilization Efficiency Rating, dependent on year

AFUE(eff) = Efficient Furnace Annual Fuel Utilization Efficiency Rating.

EFHL = Equivalent Full Load Hours for heating (hr)

¹⁸ Illinois_Statewide_TRM_Effective_060113_Version_2.0_060713_Clean.pdf

¹⁹ Illinois_Statewide_TRM_Effective_060114_Version_3 0_021414_Final_Clean.pdf (for measure errata corrections).



7.1.1.2 Space Heating Boiler Tune-Up

TRM (v2.0) Algorithm and Assumption Δtherms= Ngi* SF * EFLH/(Effpre * 100))

TRM (v3.0) Errata Correction Δtherms= Ngi* SF * EFLH/(100))

Where:

Ngi = Boiler gas input size (kBTU/hr)
SF = Savings factor
EFLH = Equivalent Full Load Hours for heating (hr)
Effpre = Boiler Combustion Efficiency before Tune-Up

Boiler Cutout/Reset Control

TRM (v2.0) Algorithm and Assumption Δtherms = Binput * SF * EFLH /(Effpre * 100)

TRM (v3.0) Errata Correction
Δtherms = Binput * SF * EFLH /(100)

Where:

Binput = Boiler Input Capacity (kBTU)

SF = Savings factor

Effpre = Boiler Efficiency

EFLH = Equivalent Full Load Hours for heating (hr)

7.1.1.3 Low Flow Faucet Aerators

TRM (v2.0) Algorithm and Assumption
ΔTherms = %FossilDHW * ((GPM_base - GPM_low)/GPM_base) * Usage * EPG_gas * ISR

Where:

%FossilDHW = proportion of water heating supplied by fossil fuel heating (100%)

EPG_gas = Energy per gallon of mixed water used by faucet with gas water heater (0.00446 therm/gal)

GPM_base = Average flow rate, in gallons per minute, of the baseline faucet "as-used" (1.2 gal/min)

GPM_low = Average flow rate, in gallons per minute, of the low-flow faucet aerator "as used" (0.94 gal/min)

Usage = Estimated usage of mixed water (mixture of hot water from water heater line and cold water line) per faucet (gallons per year as shown in the Table 7-1 below)

ISR = In service rate of faucet aerators dependent on install method (0.95)

TRM (v3.0) Errata Correction

ΔTherms = %FossilDHW * ((GPM_base - GPM_low)/GPM_base) * Usage * EPG_gas * ISR GPM_base = Average flow rate, in gallons per minute, of the baseline faucet "as-used" (1.39 gal/min) All other factors above remain the same.



Table 7-1. Illinois TRM - Faucet Aerator Water Usage Table

| Building Type | Annual Gallons Mixed water per faucet (TRM v2.0) | Annual Gallons Mixed water per faucet (TRM v3.0) |
|---------------------|--|--|
| Small Office | 2500 | 2,500 |
| Large Office | 11250 | 11,250 |
| Fast Food Rest | 6563 | 9,581 |
| Sit-Down Rest | 10800 | 15,768 |
| Retail | 2500 | 3,650 |
| Grocery | 2500 | 3,650 |
| Warehouse | 2500 | 2,500 |
| Elementary School | 3750 | 3,000 |
| Jr High/High School | 11250 | 9,000 |
| Health | 11250 | 16,425 |
| Motel | 1250 | 1,825 |
| Hotel | 875 | 1,278 |
| Other | 5000 | 5,000 |

Source: Illinois_Statewide_TRM_Effective_060113_Version_2.0_060713_Clean.pdf Illinois_Statewide_TRM_Effective_060114_Version_3 0_021414_Final_Clean.pdf (for errata corrections).