STATE OF ILLINOIS

ILLINOIS COMMERCE COMMISSION

COMMONWEALTH EDISON COMPANY

Application of COMMONWEALTH EDISON COMPANY, for a Certificate of Public Convenience and Necessity, pursuant to Section 8-406 of the Illinois Public Utilities Act, and for an Order, under Section 8-503 of the Illinois Public Utilities Act, authorizing and directing ComEd to operate and maintain a substation in Cook County, Illinois.

No. 01-0276

Surrebuttal Testimony of

FRANK FRENTZAS

Transmission Engineer Commonwealth Edison Company

OFFICIAL FILE

I.G.C. DOCKET NO. 01-0376

Exhibit No. 5

Witness

Date 350 Reporter 34

- 1 Q. Please state your name and business address.
- 2 A. Frank Frentzas, Two Lincoln Centre, Oakbrook Terrace, Illinois.
- 3 Q. Are you the Frank Frentzas who previously submitted testimony in this matter?
- 4 A. That's correct.
- 5 Q. What is the purpose of your surrebuttal testimony?
- 6 A. I will respond to Mr. Rosenberg's critique of my estimate of the cost to move ComEd's
- 7 equipment from the subject parcel to another location at Skokie TSS.
- 8 Q. Could you summarize your testimony?
- A. The estimate that I prepared is just that: an estimate. The purpose was to give the 9 Commission the means to compare the cost of purchasing the property for fair market 10 value to the cost of moving the equipment. As the Commission is aware, utilities are 11 often called upon to give engineering estimates of projects, particularly because of the 12 least-cost standard in the Public Utilities Act. We are not typically asked to explain and 13 14 justify every detail of every component of the estimate, but I used our standard methodology. That is why my initial testimony did not explain the estimate at great 15 16 length. We did, however, produce my notes and backup materials in response to data 17 requests. A copy of my notes are Attachment FF-1 to my testimony, and Attachment FF-2 is a copy of the backup materials I used. 18
- I have examined the testimony of Mr. Rosenberg, in which he concludes that

 many of the items making up my estimate were inaccurate or overstated. As I explain in

Docket 01-0276 Page 1 of 8 ComEd Ex. 5

- more detail below, Mr. Rosenberg's criticisms are erroneous, or based on a misunderstanding of my methodology and the work we would have to perform.
- Q. Mr. Rosenberg states in his testimony, at line 61, that there are four capacitors on the subject property. Is that correct?
- 25 A. No. There are two capacitors completely on the parcel, and part of a third one. There is a
 26 fourth capacitor just off the property to the north of the boundary line. This is all shown
 27 on a survey map of the parcel, Attachment FF-3 to my testimony. For the purposes of my
 28 estimate, in order to vacate the property, we would in fact have to move all four
 29 capacitors. Three of them would obviously move because they now occupy the parcel.
 30 The fourth would have insufficient clearance to possible structures on the parcel to leave
 31 it where it is.
- Q. Mr. Rosenberg states at lines 102-103 that you assumed labor costs of between \$66.90
 and \$70.40 per hour. Is that true?
- A. No, Mr. Rosenberg is confused on this. In my workpapers, to which Mr. Rosenberg refers, I was making two separate cost calculations. One calculation included indirect costs, such as overhead, which we refer to as costs pursuant to General Order 25 (abbreviated G.O. 25 in my notes). The cost estimate I described in my previous testimony was an estimate of only the direct costs associated with moving the equipment.
- 39 Q. So, what were the labor costs you actually used?
- 40 A. The costs I used for my estimate were between \$43.50 and \$49.55 per hour.

Docket 01-0276 Page 2 of 8 ComEd Ex. 5

Q. On line 109, Mr. Rosenberg says that you assumed .03 hours per foot for removal of the grounding cable, and .07 hours per foot for installation. Is that right?

A. No, it is not. Mr. Rosenberg has again become confused looking at my workpapers without understanding the methodology. Because ComEd needs to perform these estimates regularly and repeatedly, we have a standardized process for it. The way we estimate a job like this is to determine first how many plant property units the specific task will take. These are found in ComEd's Substation Unit Standards Catalog, which is attached to my testimony as Attachment FF-2. (As I mentioned earlier, we previously provided a copy of this to the intervenors in response to a data request.) So, the .03 units per foot for removal of ground cable, and .07 units per foot for installation of ground cable, which appear in my workpapers and to which Mr. Rosenberg refers, are plant property units, not hours. For all of the specific above-grade tasks that ComEd would perform, I consulted our experience-based Substation Unit Standards Catalog to determine how many units each task would take. From that, I can get a total number of plant property units for the entire project.

The next step of the calculation is to determine how many man-hours it will take to complete each unit of work. Again, this number is based on experience, and it varies from region to region within ComEd's service territory. This allows us to factor in the construction conditions, historical results, and labor conditions and rates present in the particular region. For the northern region, in which TSS 88 Skokie is located, the going rate is 2.25 man-hours per unit.

Docket 01-0276 Page 3 of 8 ComEd Ex. 5

- So, the calculation shown in my workpapers, taking the example of removal activities, is 105.3 total units times 2.25 man-hours per unit equals 236.43 man-hours to complete the removal activities.
- Q. Did you multiply your estimate of hours by 225% as Mr. Rosenberg states?
- A. No, once I calculated the estimate of the number of man-hours to complete the abovegrade portion of the project, I just multiplied the straight time by the appropriate hourly rate.
- 69 Q. Mr. Rosenberg states that installing just six feet of wire per hour is unreasonable. Is that
 70 right?
- No. There are two things to keep in mind. First, this 310 feet of grounding cable will be buried underground, 16 to 18 inches deep. So the time involved in removal includes excavation, and the installation work includes trenching. Second, it's six feet per manhour that ComEd pays for. ComEd would have a four-man crew working on this job, so the actual rate of installation would be over twenty-five feet per hour. Twenty-five feet of buried cable per hour is not unreasonable, and it's been our experience based on actual ComEd jobs.
- 78 Q. Mr. Rosenberg states on lines 134-35 that ComEd will need four new foundations, so he calculates \$8,000 per foundation. Is he right?
- No, he's not. There are six foundation structures under each of the current units, two under one side (where the capacitor is) and four on the other side (where the attached circuit-switcher is). There are four capacitors, so that's a total of 24 foundations to

Docket 01-0276 Page 4 of 8 ComEd Ex. 5

remove. If we reinstalled them in the new location, we would put two foundation structures under each capacitor, and four under each circuit-switcher, since we are reusing existing equipment. So that's six foundations per unit, or a total of 24 foundations to install. Therefore, Mr. Rosenberg's calculation of \$8,000 per foundation is inaccurate. The actual per-foundation figure is \$32,000 divided by 24, or just over \$1,300 per foundation.

83

84

85

86

87

88

- Mr. Rosenberg states at lines 139-144 that you have overestimated the amount of time needed for excavation. Is he right?
- 91 A. No, it is Mr. Rosenberg who is in error. He has forgotten to take into account two things.

 92 First, the excavation will not be accomplished with a machine alone; some of this work

 93 will have to be done by hand. It is standard practice to hand dig inside a substation yard

 94 close and around live cables for safety and reliability concerns. Second, Mr. Rosenberg

 95 is only thinking of the excavation needed to remove the old foundations. In fact, there

 96 would be significant excavation at the new location before installation could proceed.

 97 My estimate is reasonable for this work.
- 98 Q. At lines 145-49, Mr. Rosenberg says that you have overestimated the cost for finish yard 99 stone. Is it true?
- It's not true. For finish yard stone, our company specification is to use compacted, CA-6 limestone for this kind of project. Using "cheap stone," as Mr. Rosenberg puts it, would likely result in areas with ruts from truck traffic, and we don't want that. Again, Mr. Rosenberg has clearly forgotten the installation part of the project. Much of the stone would be in the area of the relocated equipment, and Mr. Rosenberg has only focused on

Docket 01-0276 Page 5 of 8 ComEd Ex. 5

- the locations of the old foundations. My estimate is reasonable and in line with our recent projects of this type.
- 107 Q. Mr. Rosenberg states that you added costs for restoration of the landlord's property, and didn't need to.
- Well, perhaps he's partly right on that one. It is customary for us to leave the property in pretty good shape when we turn it over to someone, so I included in my estimate some expenses for that work. If the landowner didn't want us to do that, it's true that we could save a few dollars. I should point out, though, that some towns require some amount of work to avoid unsightly lots.
- 114 Q. So, would you reduce your estimate by \$7,863?
- No, even if we're allowed to leave the parcel "as is," the reduction would be less that.

 We will not be able to avoid all of the \$7,863 included in my estimate for hauling away excavated material. It must be remembered that we will need excavation, and therefore hauling, at the site of the relocated installation.
- 119 Q. Why did you add 10% for contingencies?
- This is a standard feature of our estimates, because there are many things, including
 weather related problems, outages and other unknowns that could be in the ground
 (railroad tracks, old foundations, etc.) that we cannot control. Contingencies are a fact of
 life in managing construction projects.

Docket 01-0276 Page 6 of 8 ComEd Ex. 5

- 124 Q. Is it inappropriate to apply the contractor's overhead and profit of 20% to the total

 125 amount including the contingencies?
- 126 A. No, my calculation is correct. Let's say bad weather or an outage delay forces the
 127 contractor's crew to wait for a couple hours or more before restarting their work. They
 128 still pay the workers for the time they wait, and that comes out of the 10% contingency.
 129 It is quite appropriate to assume that the contractor will charge us profit and overhead on
 130 the whole amount, including amounts in the contingency.
- 131 Q. Mr. Rosenberg says that "engineering" and "contract services" are the same thing, and
 132 suggests that you are double-counting them. Is that true?
- No, Mr. Rosenberg is mistaken. Engineering work is work performed before the construction, such as designing the relocation and working up the necessary construction drawings. "Contract services," is an inspector to provide field inspection services while the construction work is under way. The two tasks are not the same thing, and we will have to pay for them both to complete the project.
- 138 Q. What do you conclude about Mr. Rosenberg's estimate that the cost to move the four capacitor banks would really be about \$111,000?
- Mr. Rosenberg's estimate is unrealistically low. If we really thought we could move the cap banks for that amount, we'd probably go ahead and do it and be done with this dispute. But we cannot.
- 143 Q. Have you checked your work in any way?

Yes, I asked one of the contractors we've worked with in the past to give me an estimate 144 for the foundation work for relocating the four capacitor banks and four circuit switchers. 145 He gave me an estimate of \$67,000. This is roughly consistent with my estimate for the 146 same work. My estimate was \$77,209, but I was including approximately \$8,000 for 147 finishing of the subject property. In the contractor's estimate the subject property would 148 be backfilled with the excavated materials if this is acceptable with the owners. In light 149 of Mr. Rosenberg's testimony suggesting that no finishing was necessary, I asked the 150 151 contractor not to include it.

- Does this conclude your testimony?
- 153 A. Yes, it does.

ATTACHMENT FF-1

75588 SKOKIE RELOCATE 4-18 MUAR TERTIARY CAPACITOR BANKS

> CONTRACTOR TOTAL \$ 121,474. CONFLD ENG & CONT. SUCT \$ 20,216

ComED 55C \$ 84,400 " ENGING 6,500 " TAD 16,100

TOTAL (6.0.25) \$ 248,690 PRIVECED COST (12001 #)

CONTRACTOR TOTAL \$ 121,474 GONEO ENG & CONT. SYCS \$ 20,216

COMED SSC \$52,080 11 ENG \$ 4,955 11 TAD \$ 11,892

TOTAL (DIRECT) \$ 210,617

Attachment FF-1

TES 88 SKOKIE RELOCATE 18 MVAR TERT. CAP BKS 84-3, 84-4, 84-5, 84-6

GUTTEM	RemŲU.	Ren Units	Iws/U	INSTELLE TO	MATE
4-18 MUAR TERT. CAP. BK	i3.5	54.0	40.5	162.0	*****
12- C/s Phases	3.5	42.0	7.0	84.0	
310-GROUNDING (R-500/I-300)(FW LL)	6.03	9.3	6.07	21.7	36
4- OPOR. Pes 17:10+5 (49/4)	-		3 . 5	14.0	19.
12- GRD RODJ (11ex)	~		0.5	6,0	/3:
sz-melyz	-	_	1.0	25.0	43,
925 - la DC PWR & Co or (41.66/1)	-	_	6,03	27.75	/53
495- Ce-DC Pun (76-53/)	_	-	6.03	i4 .85	41
495'- a- Sada (\$0.761)	_		0.03	14-85	<i>3</i> 7:
6657- Ca- AC Pur (50.38/1)		_	6.03	19.95	25、
310'- TRank GOD CA	. —	-	6.03	9.3	
400 - Direct Bury Pure Cour.	-	_	6.67	28.0	
		/05.3u		427.40	¢ 370¢
<i>•</i>		× 2.25 mb/L		x 2.25 mh/c	-18. 37E
	_	236,93 h		96 1.65 hr	\$4070

Somm RRY				_	DIRECT
(SSC (961.45+236.53)	=	i198.58 mi	×	G.0.25° 70.40° 84 380	
LABOR (8%, 55c) LABOR (8%, 55c) TAD (25% 55c)	Ξ	95.89 mh	X	* 66.99 = 6.424	x 49.55
			×	866.99 = 16,059	x 49.55
Mintl { \$4070 × 1.510 =	£ 6	145.70			

29.502/6/01

BELOW GRADE ESTIMATE

LOCATION: TSS 88 SKOKIE

1.	Miscellaneous Equipment Fdns. including formwork, reinforcing steel,concrete & anchor bolts =	\$31,986
2.	Concept Building Foundations Including formwork, reinforcing steel, & concrete =	\$0
3.	Excavation and Backfill =	\$25,730
4.	Clay fill brought in and compacted =	\$0
5.	Granular Fill brought in and compacted =	<u>\$0</u>
6.	Finish Yard Stone =	\$11,630
7.	2 Transformer foundation complete with fire protection fill =	\$0
8.	Installation of owner furnished Elec. Manholes =	\$0
9.	Installation of owner furnished troughs =	\$0
10.	Site drainage-sewers, manholes, catch basins, oil stop valves, etc. =	\$0
11.	Fencing (6' chainlink fence + 1' of barbed wires) =	\$3,168
12.	Spread Topsoil from stockpile and seeding =	\$2,899
13.	Haul excess excavated material off-site =	\$7,863
14.	Conduit Work (per attached worksheets) =	\$6,000
15.	Excavation and Backfill for grounding =	\$2,750
	TOTAL = Add 10% for Contig.= Contractors Overheac and profit add 20% = Add 10% for Engg. = Add 10% for Contract services =	\$92,026 9,203 \$20,246 \$10,122.86 - \$10,122.86
	CONTRACTOR TOTAL =	\$121,474
	GRAND TOTAL ■	\$141,720

ATTACHMENT FF-2

March 25, 1993

To: SEED Engineers

Subject: Escalation Rate for Estimating

The current escalation rate for estimating future expenditures is 4.5%. This rate has been in effect since August, 1992. As in the past, a different escalation rate can be used if it can be documented by a purchase contract or other means.

Frank Kofron

cc: J. Castillo
D. J. Ziebell

FJK/ZPET-6764

FOR TYPICAL PROJECTS

PER GO-25, ENGINEERING FOR SUBSTATION PROJECTS = *** 95

TOTAL LABOR DOLLARS SHOWN IN ESTIMATING BOOK INCLUDE A 42% BURDEN FOR OAD, SUPERVISION AND TRANSFORTATION.

THEREFORE:

TOTAL CONSTRUCTION DOLLARS		.09	
	X		= ENGINEERING MANHOURS
CURRENT LABOR RATE		1.42	

AS OF JULY 10, 1992, CONSTRUCTION LABOR RATE IS \$35.15 per MANHOUR. ENGINEERING LABOR RATE IS \$38.50 per MANHOUR.

ESCALATION	HULTIPLIER	4.5% per year	0.045	9-24-91
1 year 2 years 3 years 4 years 5 years 6 years 7 years 8. years 9 years	1.0450 1.0920 1.1412 1.1925 1.2462 1.3023 1.3609 1.4221 1.4861 1.5530	· .	WORK SHEET ENGRMHR	NAME

STIMATING DECS. INGINEERING HANHOURS AND COSTS TOR TYPICAL PROJECTS

PER ID-IS. ENGINEERING FOR SUBSTATION PROJECTS = 14% OF TOTAL CONSTRUCTION HANHOURS

TOTAL LABOR DOLLARS SHOWN IN ESTIMATING BOOK INCLUDE A 42% DURDEN FOR DAD. SUPERVISION AND TRANSPORTATION.

THEREFORE:

TOTAL CONSTRUCTION DOLLARS		.09	= ENGINEERING MANHOURS
CURRENT LABOR BATE	X .	1.42	- 1,110 x110 3110

AS OF JULY 10, 1992, CONSTRUCTION LABOR RATE IS \$35.15 per MANHOUR. ENGINEERING LABOR RATE IS \$35.10 per MANHOUR.

 سريفرت

February 5. 1987

To: E. F. Burns

G. Snell

D. P. Brown

G. E. Bogdan J. P. Rossi

L. D. Gillette

Subject: UPDATED SUBSTATION UNIT STANDARDS CATALOG

Attached is a complete copy of the current Substation Unit Standards Catalog. This catalog contains the current performance values that are to be used to calculate manhours per unit for all substation work orders. effective 1/1/87.

If you have any questions, please call me on Extension 8351.

E. J. Ruthenberg
Division Operating Services

ER/ac

Attachment

cc: A. P. Ehardt

D. J. Frasher

J. B. Gunneil

J. P. Molitor

R. A. Schrage

W. J. Specha

B. E. Willemsen

A. Wroblewski

٠,

Substation Unit Standards Catalog

The Substation Unit Standards Catalog is issued by Division Operating Services. 38FNW.

The catalog is issued to the Substation TJM Coordinators in each Division. Station Mechanical Engineering. Station Electrical Engineering and T & D Construction.

Please refer all questions about this catalog to:

Substation Construction TJM Coordinator
Division Operating Services
Extension 8351

Substation Unit Standards Catalog

Check List

PAGE	LAST REVISION DATE
Check List	1/12/87
Index	1/12/87
1	07/86
2	10/86
3	10/86
4	10/86
5	10/86
6	01/85
7	10/86
· · · · · · · · · · · · · · · · · · ·	01/86
B	01/96
9	01/86
10	
11	01/86
12	
13	10/86
14	
15	
16	
17	
18	
19	04/85
20	
21	04/86
22	
23	
24	
25	
26	
27	
28	
25	
30	

SUBSTATION UNIT STANDARDS CATALOG

TABLE OF CONTENTS

				PAGE
Code	2	_	Transformers	
	_			•
			a. Transformers (Oil & Askeral Filled)	i
			b. Phase Shifters	1
			c. Transformers (Network Type)	2
			d. Network Protectors	2
			e. Network Fuse Mounts	2 2
			f. Network Fuse Mount Cover	2
			- Deservice Transformers	2
			h. Transformers (Dry Type) & Station Light & Power	2
			i. Thermal Shorting Device	
			i. Fans	
			k. Transclosure Housing	3 3 3
			1. Low Side Cable Compartment	3
				4
Code	3	-	Regulators	
Code	A	_	Circuit Breakers	5
Code	6	-	Switchgear and Associated Switching Devices	
			·	6
			a. Metal Clad/Metal Enclosed Switchgear	٠ .
			b. Air Circuit Breakers	,
•			c. Wall Mounted Bays	<u>ر</u> ج
			d. Wall Mounted Cabinets	6 6 6
			e. Sectionalizer	୍ଟ '6
			f. Bifurcating Cabinet	•
.	_		outern Timing Equipment:	
Code	•	-	Current Limiting Equipment	
			a. Arresters	7 7 7 7
			b. Inductor Dry	7
	•		c. Meutral Inductor	.7
			d. Resistor	7
			e: Capacitors	7
			4	
Code	8	-	Switchboard, Control & Communication	
				8
			a. Relays	8 8 8 8
			b. Relay Panels	a a
			c. Meters	8
			d. Signal Jevice	
			e. Switchboard - Panel - Cabinets	9
			f. Supervisory	10
			g. Load Control Equipment	10
			h. Carrier Current Equipment	11
			1. Audio - Tone Equipment	
			j. Microwave Equipment	11
•			k. Miscellaneous (Panels, Breakers, Switches)	

SUBSTATION UNIT STANDARDS CATALOG

TABLE OF CONTENTS (continued)

Code	9	_	Instrument Transformer	PAG
			a. Transformers	12
			b. Pole Mounted Primary Metering Cluster	12
Code	: 11	: -	Disconnect Switch	
			a. Switches	13
			b. Cutouts	13
			c. Live Parts	13
Code	12	: -	Control/Power Cable, Connections, Bus Work	
			a. Bus Support/Insulators	14
			b. Lug/Connectors	14
			c. Grounds	14
			d. Bus	14
			e. Cables - Control, Power, and Ground	15
			f. Cable Joints	16
			g. Cable Terminations	17
			h. Trenching	18
			i. Miscellaneous (Alarms, Fans, Indoor Light Fixtures,	
			Indoor Switches)	18.
			j. Weights of Copper Pipe, Bar, or Rod	19
Code	14	-	Conduit and Piping	
			a. Conduit	20
			b. Troughs	20
			c. Fittings	20
			d. Excavation	21
			e. Miscellaneous (Brackets, Supports, Core Drilling,	~•
-			Ladders, Pumps, and Unistrut)	21
Code	15	-	Outdoor Structure	
	•		a, Weights of Steel, Plate, Tube, Bar, Angle Iron	22
			b. Bus and Switch Structure	23
			c. Anchors, Guys, Arms	23
			d. Miscellaneous (Spare Fuse Cabinet, Outdoor Light	
			Fixture, Pipe/Angle Iron Frame Work,	
			Outdoor Safety Switch)	23
			e. Miscellaneous Steel Structure Weights	24
Code	::	-	Foundation and Yard Work	
			a. Foundations, Footings, Caissons	25
			b. Miscellaneous (Bases, Slabs, Gravel)	27
Code	19	_	Storage Batteries and Charging Sets	28

SUBSTATION UNIT STANDARDS CATALOG

TABLE OF CONTENTS (continued)

Code	19 -	Auxiliary Equipment	PAGE
		a. Miscellaneous (Anodes, Telephone, Battery Light, Generators)	29
		b. Fire Equipment	29
Code	28 -	Fencing and Vault Slab	
		a. Fencing and Slabs b. Barriers and Guards	30 30

SUBSTATION UNIT STANDARDS

(CODE 2) TRANSPORMERS

Reporting Unit is Per Each Item

-

Transformers (Oil and Askeral Filled) Includes Pad-Mount Type

Note: Unit value for transformers includes bushings, radiators and fans not field mounted. Does not include lightning arresters and low side cable compartment.

		Unit St	andards Three F	hace
12 KV and 34 KV KVA	Single Install		<u>Install</u>	Remove
100 - 250	4.5	2.0	9.0	4.5
333 - 750	5.5	2.5	11.0	5.5
1.000 - 2.500	6.5	3.0	12.5	6.0
3.750 - 6.250	0.5	3.0	20.0	10.0
7.500 - 10,000			25.0	12.0
12,000 - 15,000			30.0	15.0
69 KV and 138 KV				
RVA	<u>Install</u>	Remove	<u>Install</u>	Remove
7.500 - 10.000	80.0	40.0	162.0	80.0
12.000 - 20.000	112.0	60.0	225.0	112.0
33.000 - 40.000	140.0	70.0	300.0	150.0
45.000 - 60.000	180.0	90.0	395.0	198.0
65,000 - 80,000	225.0	110.0	485.0	243.0
345 KV and 765 KV				
•.			<u>Install</u>	Remove
300 MVA (per Three			648.0	405.0
333 MVA (per Single			648.0	405.0
500 MVA (per Single Unit Transformer	Phase Tra	insformer)	648.0	405.0
	źha	se Shifters		
	<u> </u>		Install	Remove
Phase Shifter, single	tank mount	1.5	648.0	405.0
Fhase Ellifter, two tan	k mounting		950.0	405.0
•	<u> Transforme</u>	rs (Network	Typel: & 2	
Dil. Askarel & Silicon	e Filled		<u>Install</u>	Remove
All Sizes			13.0	5.2

For installation or removal in buildings-multiply unit values by 1.5. See vault slab on page 30

Revised 7.66

12/17/85

(CODE 2) TRANSFORMERS (Continued)

Network Protector

<u>KVA</u>

AMP		<u>Install</u>	Remove
_	<u>ئ</u> خ	7.5	4.5
800 - 1.60C		12.0	7.0
1.800 - 2.250		15.0	10.0
2.500 - 3.000		25.0	16.0
3,500 - 3,900 Protector Housing (Field Assembled)		18.0	13.0
Balancing Transformer		27.0	7.1
Network Fuse Mounts		4.5	2.0
Network Fuse Mount Cover		3.0	1.5

Portable Transformers

Portable Transformers - Includes fence and cables, installation & removal.

34Kv	30	units
138KV - 20 MVA	75	units
- 40 MVA	125	units

Transformers (Dry Type) & Station Light and Power*

	Unit	Standards	
Single	Phase	•	Three
<u>Install</u>	Remove	<u>I</u>	<u>nstall</u>

5	_	25	2.5	1.0	3.0	1.0
35	_	100	3.0	1.5	3.5	1.5
150		• • •	4.0	1.5	5.0	1.5
300			9.0	2.5	11.0	2.5
		1.000	10.0	3.0	13.0	3.0
		2,000	11.0	3.5	15.0	5.0
		and larger	13.0	5.0	20.0	6.5

^{*}For installations or removals in buildings - multiply unit values by 1.5.

Thermal Shorting Device (Field Installed)

		Install	KEMOVE
Single Phase Three Phase		1.0	. 50 . 50

Phase

Remove

(CODE 2) TRANSFORMERS (Continued)

Transformer Fans (Field Mounted)		Unit Standards		
<u>.</u>	7e-	Install	Remove	
Per fan		.9	. 2	
Transclosure Housing for Transformer (Per Unit)		<u>Install</u>	Remove	
Unit/Bay/Cubicle		3.5	1.5	
Low Side Cable Compartment		<u>Install</u>	Remove	
Cable Compartment-Low Side		7.0	3.5	

(CODE 3) REGULATORS

Reporting Unit is Per Each Item

					Unit S'	tandards	ree Phas	
	<u>KVA</u>		<u>Si</u> Install	ngle Pha Remove	se Replace	<u>Install</u>	Remove	Replace
24 37 51 97 168 376	- -	35 50 96 167 375	9.0 10.0 13.0 16.5	2.0 2.5 3.0 4.0	9.0 10.0 13.0 16.5	25.0 27.5	7.5 10.0	25.0 27.5

(CODE 4) CIRCUIT BREAKERS

Reporting Unit is Per Each Item

				<u>U</u>	nit_Stand	ards	
011-			Sincle	Phase			Phase
<u>kn</u>			<u>Install</u>	Remove		<u>Install</u>	Remove
4			8.0	5.0		20.0	10.0
12			10.5	5.5		21.0	10.5
34	•		21.0	10.5		42.0	21.0
69			25.0	12.5		72.0	19.0
138			59.0	30.0		118.0	60.0
345			287.5	142.5		575.0	285.0
Air	(see notes	: * }					
<u>KV</u>	,		<u>Install</u>	Remove		Install	Remove
. €	S .		2.0	1.0		3.5	1.5
4			3.5	2.0		7.0	3.5
12			4.5	2.5		9.0	4.5
34			9.0	4.5		18.0	9.0
		6					,
<u>KV</u>	Blast and	<u>SF</u>	•			<u>Install</u>	Remove
12 34					•	£	
138							
345 765					•	287.5 425.0	144.0 212.5
				•		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
	cser. 011-1						D 1
<u>ka</u>	<u>Install</u>	Remove	Replac	<u>e</u>	<u>Install</u>	Remove	Replace
4	8.0	2.0	8.0		16.0	4.0	16.0
12	10.0	2.5	10.0		20.0	5.0	20.0
34	16.0	5.0	15.0		32.0	10.0	32.0
CIRC	UIT SWITCKS	:s					
<u>kv</u>		_				<u>Install</u>	Remove
34						7.0	3.5
138	(Per Phase)		2	-		18.0	9.0
	Cperators		•	-		15.0	8.0
	• · · · · · · · ·						

^{*}Air circuit breakers which are a component part of the switchgear are shown on Page 6.

(CODE 6) SWITCHGEAR AND SWITCHING DEVICES

Reporting Unit is Per Each Item

Metal Clad/Metal Enclosed Switchgear	Unit Sta	
ESS Station - Trans. Loc CTLY - Switchgear	Install	Remove
Four bay group or less including control bay	10.0	5.0
Additional manual bay (per bay on new construction) 3.5	2.0 2.5
Additional control bay (per bay on new construction	15.0	2.5 5.0
Addition to existing switchgear (per bay)	19.0	3.0
TSS - TDC - DC Switchgear	11	
Per Bav	<u>Install</u>	Remove
Addition to existing switchgear	24.0	8.0
Additional bay (new construction)	15.0	5.0
Shelter or aisle switchgear (additional per bay)	4.0	2.0
Air Circuit Breakers		
(Component Part of Switchgear)	_	_
<u>kv</u>	<u>Install</u>	Remove
. 6	3.5	1.5
4	4.5	2.0
12	6.0	3.0
34	18.0	9.0
Wall Mounted Bays (Metal Clad) Minirupter	<u>Install</u>	Remove
Per Unit	22.0	9.0
Wall Mounted Cabinets (Benelex type material)	<u>Install</u>	Remove
Type		
All	12.0	6.0
Sectionalizer (Padmount type)	<u>Install</u>	Remove
Single Phase -	3.0	1.0
Three Phase	5.0	2.5
Bifurcating Cabinet*		
•	<u>Install</u>	Remove
Bifurcating Cabinet	10.0	5.0

^{*}Foundation not included

Revised 1/86

à

(CODE 7) CURRENT LIMITING EQUIPMENT

Reporting Unit is Per Each Item

	_	Unit St	<u>andards</u>
Arrester		Install	Remove
<u>KVA</u>			-
		1.0	. 2
4 and under		1.0	. 3
12		1.5	. 5
34		2.0	1.0
69		2.5	1.5
138		3.5	2.5
345		5.0	3.5
765		3.0	
Inductor			
Dry			
			- E
Single Phase		7.5	2.5
Three Phase (Stacked)		23.0	7.5
, , , , , , , , , , , , , , , , , , , ,		_	
Neutral Inductor		7.5	2.5
11001101			
Transformer Neutral Inductor Switch			
Enclosure		9.0	3.0
138 KV Oil-Filled Inductor -			
Single Phase		275.0	150.0
138 KV Oil-Filled Inductor -			
Three Phase	•	325.0	160.0
765 KV Oil-Filled Inductor -			•
Single Phase		648.0	405.0
Single rhase			
Decises			
Resistor			-
11		36.0	13.0
Neutral 4/12 KV			
•			
Capacitor			•
12024 a n			
KVAR			
	1	10.5	5.5
225 - 1.800 12 KV Sw. Assembly (C8254	(17.5	8.0
2.100 - 12 KV Sw. Assembly (C8254	(32.0	12.0
6.000 12 KV Met. Encl. (EM22004	,	30.0	10.0
6.000 12 KV Cp. Rack (EM22002)		34.5	11.5
14.400 34 KV Op. Rack (EM22001)		40.5	13.5
18.000 34 KV Op. Rack (EM22003)		40.5	
Individual cell added to or removed fr	om.	_	-
a rack (each)		. 5	5
, .			

(CCDE 8) SWITCHBOARD, CONTROL & COMMUNICATION

Reporting Unit is Per Each Item

Relay - Includes drilling, sawing, mounting and installing	2	Unit Sta Install	
All Aux. Relays - Surface mounted lik Eagle. Clare/Telephone/ Amphenal Sock /Socket (HMA) used with Reed relay/ Wilmar relay/Durakool (includes accessory fitting)/Adlake	et	2.5	1.5
All other Relays	(each)	6.0	3.0
Relay Panels Solid state phase comparison relay panel (1' x 19" x 30")		9.0	3.0
<u>Meter</u>			
Ammeter, recording or indicating		5.0	1.0
Ammeter, thermal		5.0	
Voltmeter, recording or indicating			1.0
Other meters		5.0	
Reactive Volt/Varmeter		5.0	
Watt-hour		5.5	
Wattmeter - Varmeter (totalizer)		9.0	1.5
Signal Device	•		•
Annunciator, 4 to 20 points.		14.5	4.5
for each additional point, add .2			_
Horn or bell		2.5	. 5
Indicating lamb receptable (EM 12305)		. 5	. 7

(continued)	Install	Bancua
	Install	Remove
Switchboard - Panel - Cabinet		
A.C. Lighting Distribution Panel	9.0	2.0
Alarm Panel	9.0	2.0
Auto Transfer Cabinet		12.0
•	36.0	9.0
Control Switchboard Data Acquistion Panel (control type-		
remote) For additional point, add .2	36.0	9.0
D.C. Distribution Panel Board		2.0
	9.0	
Differential Relay Cabinet	36.0	
Economic Generator Control (E.G.C.)	15.0	5.0
Main A.C. Power Panel Board	20.0	
Motor Control Center (includes cabinet)	30.0	15.0
Number of breakers - 16	33.0	
25	36.0	
30	18.0	5.0
Auxiliary Steel Panel	18.0	2.0
Relay Panel. Hinged. Steel	9.0	2.0
(Approx. 26" x 21" x 12")	9.0	2.0
Primary Metering Cabinet		
(Approx. 42" x 52" x 48") includes	9.0	2 0
(3) 12 KV Cts and meter sockets	36.0	
Telemetering Panel	5.0	
Bonding Switch Cabinet	9.0	
Recording Ammeter Cabinet (EM 11234)	36.0	9.0
Relay Switchboard Relay Panel	30.0	9.0
Scada RTU Data Processing Cabinet:		10.0
one bay remote	40.0	
two bay remote	50.0	
three bay remote	60.0	
Transformer Overload Relay Cabinet (tor)	9.0	2.0
Transformer Paralleling Cabinet	9.0	2.0
Generator Control Console (3' x 2' x 4')	18.0	5.0
Underfrequency Cabinet	9.0	2.0
בעפבפעובספע-		
Master Station		
One cabinet with the capacity of four	10.0	4.0
sets. Cabinet and twenty points	10.0	₹.0
- each additional point, add .:		
Remote Station with swinging rack		
One capinet with capacity of up to		
forty points. Cabinet and twenty points	:8.C	8.0
- each additional point, add .C	, -	•
•		

(CODE 8) SWITCHBOARD, CONTROL AND COMMUNICATION (CONTINUED)

Notes: Western Electric Corp., Visacode. Radac and Harris Control Supervisory sets are all alike.

Master set requires - one communication cable one A.C. cable one D.C. cable

Remote set requires - one cable for each point installed one communication cable one A.C. Cable One D.C. Cable

All supervisory sets are floor mounted

Reporting Unit is Per Each Item	Unit Sta	andards
Special Instrument and Device	Install	
Special instrument and bevice		
Frequency Indicator	9.0	2.0
Oscillograph with Cabinet	36.0	9.0
Oscillograph only (Replacement)	9.0	2.0
Power Factor Indicator	9.0	2.0
Speed Indicator	9.0	2.0
Synchroscopes	9.0	2.0
Synchroscopes		
Took Control Equipment	Unit St	andards
Load Control Equipment	Install	
		•
Amplifier	6.0	2.0
Impulse Converter	6.0	2.0
Indicating Control	6.0	2.0
Power Supply	6.0	2.0
Watt Var/Transducer	2.0	1.0
Telephone Printer	4.5	1.0
Totalizer Control	9.0	3.0
Transmitter	13.5	4.5
Voltage Regulating Blasing Cabinet	9.0	3.0
voltage Regulating Blasting Cabinet		
Commission Current Familianos	Unit St	andards
Carrier Current Equipment	Install	
Amplifier Unit (T.T. KMTR.)	3.5	1.5
Aux. Equipment Panel (Control Panel)	3.5 -	1.5
Carrier Current Alarm Bell	1.5	. 5
DC Switch and Fuse Panel Unit	3.5	1.5
Hybrid Unit	3.5	1.5
Initiat.or Respond.Check Back Device	3.5~	1.5
Line Tuner	3.5	1.5
Modulator Unit	3.5	1.5
	3.5	1.5
Power Supply Unit RCVR Unit	3.5	1.5
	40.0	16.0
Swinging Rack Cabinet with Components	22.0	11.0
Wave Trap	3.5~	1.5
MMTR/RCVR Unit	2.5	

10

Revised 11/86

12/17/85

(CODE 8) SWITCHBOARD, CONTROL AND COMMUNICATION (CONTINUED)

Audio-Tone Equipment	Unit Sta Install	
Aux. Equipment Panel Unit D.C. Switch & Fuse Panel Unit Initiat.or Respond.Check Back Device Modules (T.T. or D.C.R.) Swinging Rack Cabinet with Components	3.5 3.5 3.5 3.5 40.0	1.5 1.5 1.5 1.5
Telephone Cabinet (large) Fiber Optic Modem	18.0	9.0 .2
Microwave Ecuipment	Unit Sta Install	
8 ft. Equipment Rack 4 ft. x 8 ft. Plywood for	1.0	. 5
Demarcation Cabinets	1.5	. 5
Wave Guide (per ft.)	.1	. 1
Wave Guide Connector	1.0	. 5
Wave Guide Ice Shield (per ft.)	1.0	. 5
Miscellaneous	Unit Sta	ndards
	<u>Install</u>	
Alarm Panel (all EM 47000 Series) Avalanche Diode	9.0 .1	2.0
		-1
Circuit Breaker (100 Amp. & Under)	1.0	. 5
Circuit Breaker (over 100 Amps. to 400 Amps.)	2.0	. 5
Circuit Breaker (over 400 Amps. to 600 Amps.)		1.0
Contact Making Clock	4.5	1.0
Contact Making Voltmeter	4.5	1.0
Control Switch (SBM type switch)	2.5	1.0
Current Shorting Swtich	1.5	1.0
Flexitest Switch	5.0	2.5
Fuse Block/Base	1.5	1.0
Line Drop Compensator	4.5	1.0
Motor.Starter	5.5	1.0
Phasing Transformer 120 V	4.5	1.0
Push Button Station	1.0	. 5
Resistor, Instrument (3600 OHM or less)	. 5	. 2
Resistor, Instrument (over 3600 OHM)	. 8	. 3
Rheostat, Potentiometer	. 5	. 2
Switch, test	1.5	1.0
Switch, toggle	.5	. 2
Switch, knife (under 50 Amps.)	1.0	. 5
Switch, knife (60 Amps. or over)	1.5	1.0
Switch. Relay "WL"	3.0	
Terminal Block		2.0
Thermal Converter	1.5	1.0
	5.5	2.0

(CODE 9) INSTRUMENT TRANSFORMER

Reporting Unit is Per Each Item

- Current Transformer
- 2. Potential Transformer
- 3. Coupling Capacitor & Bushing
- 4. Potential Device
- 5. Cascade Potential Device
- 6. Eushing Potential Device

1917	Unit Standards	
<u>kā</u>	<u>Install</u>	Remove
.6 (switchboard type)	2.0	1.0
· · · · · · · · · · · · · · · · · · ·	4.0	1.5
4	4.5	1.5
12	9.0	3.0
34	10.0	3.5
69	13.5	4.5
138	17.0	6.5
345 765	30.0	15.0
Bushing Potential Device	8.0	4.0
Pole Mounted Primary Metering Cluster (includes Pots and Cts)	4.0	2.0

Note: Construction units are not applied when item is integral with other equipment: as in switchgear, power transformers, circuit breakers, etc.

(CODE 11) DISCONNECT SWITCH

Reporting Unit is Per Each Item

Switches (unit value per phase)		Unit Standards	
<u>KV</u> -	<u>Install</u>	Remove	
Under 12	1.5	. 5	
12	2.5	. 5	
34	5.0		
69	10.0		
138	14.5	7.0	
345	29.0	14.5	
765	50.0	25.0	
5 block			
Gas blast equipment (138/345 KV)	50.0	20.0	
3 phase unit EM 16006 Hand-operated control	4.5	2.0	
Motor-operated control	14.0	7.0	
Fuse Mounts/Cutouts (unit value per phase) <u>KV</u>			
Under 12	1.5	. 5	
12	2.0	. 5	
34	4.0	1.0	
69	6.0	2.5	
138	8.0	3.0	
Live Parts (unit per phase)			
All voltages (C 9876)	1.0	. 5	

(CODE 12) CONTROL/POWER CABLE, CONNECTIONS, BUS WORK

Reporting Unit is per Each Item Unless Otherwise Noted

Bus Support/Insulator/Strain KV	<u>-</u>	Unit Sta Install	
4 12 34 (per stack) 69 (per stack) 138 (per stack) 345 (per stack) 765 (per stack)		.5 .7 1.0 1.5 2.0 3.0 4.5	.2 .5 1.0 1.5 2.0
Lug/Connector Straight/Tee (compression (Smaller than 1/0 included with cable un			
Bar taps/crimpets/ampacts 1/0 - 500 MCM 636 - 1.000 MCM 1.113 - 2.338 MCM Bus Limiter Cable/line limiter		.1 .2 .4 .8 3.0	1.5
Rod. Ground		. 5	-
Grid. Ground (EM 24150/1)		3.5	-
Attachment, Ground (C 750/1)		1.0	. 5
Bus. Eare Copper (See Page 19 for Weights	s)		
Bar (unit value per pound) Rod and tube (unit value per pound)		.20	.10
See attached sheets and for coppe	r 155	<u>o</u>	
Bus. Aluminum Tube (unit value per foot)			
1" to 2" 1 1/1" to 3 1/2" 4" to 5" 5 1/2" to 6" Welded fittings (per weld) Bus. Aluminum Angle (per foot) Premoided Bus (C1660). (per phase)		.40 .50 .60 .70 1.0 .40	.10 .10 .10 .10
Bus Eupport Expansion Coupler (Bolted)			•
All sizes	each	. 9	. 5

P)

(CODE 12) CONTROL/POWER CABLE, CONNECTIONS.	BUS WORK	
(continued)	0112 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
(concruder)	<u>Install</u> <u>Remove</u>	
Difficulty Factor (Install & Remove)		
High Rise (Vertical Installations)	1.5 times cable us	lits
Generating Stations (Larger than 4/0 in	1.3 times cable u	lits
Main Building Only)		
Lead Covered Power Cables in Substations	1.5 times cable un	11.15
Cable Pan Covers (per foot)	.01 .01	
Cable Reporting Unit is Per Each Foot	Install Remove	
Types of Cable	<u>Install</u> Remove	
Cable. Control		
	.02 .01	المسالم
One conductor	.03 .02	
Multi Conductor	.00	
Cable, Power		
1/C 250 KCMIL & Smaller	•	
600 volt	.03 .02	·
12KV	.05 .03	
1284		
1/C 266 KCMIL - 1000 KCMIL		•
70 - 200 - 1.011.	-	
60C volt	.05 .03	
12KV	.07 .05	
34KV	.08 .06	
		2,
1/C 1113 KCMIL thru 2000 KCMIL	•	
	.10 07	()
12XV	.12 .08	
34KV	• • •	
1/C Darger than 2000 MCMIL		
.70 Ja:de: 1a.: 2000		
12XV	.12 .08	•
M/C 250 KCMIL & Smaller	•	
600 volt	.04 .03	
:2KV	.05 .03	•
•		
M/C 256 KCMIL thru 1000 KCMIL		
	.07 .05	
600 volt	.10 .07	•
:2%V	. 10	
and the second of the second o		
Cable Bare/WR/Lead Slad		
1	.03 .02	
1/C 050 KCMIL & smaller	.07 .03	
1/C 260 KCMIL - 1000 KCMIL	.10 .05	
1/C 1113 KCMIL thru 1000 KCMIL	.12 .06	
Larger than 2000 KCMIL		

(CODE 121 CONTROL/POWER CABLE, CONNECTIONS, BUS WORK (CONTINUES)

Cable Joints

Straight		. Dn:	t Standar	'ds
1/C thru 500 KCMIL			Remove	
4KV and 12KV non le 4KV and 12KV lead o		1.0	0.0 .75	0.0
1/C over 500 KCMIL				
4KV and 12KV non le 4KV and 12KV lead c	-	2.0 4.0	0.0 .75	0.0
M/C thru 500 KCMIL				
4KV and 12KV (each)		10.0	1.9	2.5
M/C over 500 KCMIL				
4KV and 12KV (each)		10.8	1.9	2.7
Trifurcating Joint				
Straight Thru 500	•		•	
4KV and 12KV (each)		10.2	1.9	2.6
Over 500 4KV and 12KV (each)		11.0	1.9	2.8
<u>WYE (Y)</u> Thru 500				
4KV and 12KV (each)		14.1	1.9	4.2
Over 500 4KV and 12KV (each)		15.2	1.9	4.5
Cable End Cap (insulated	±)			
1/C 4KV and 12KV M/C 4KV and 12KV	4	2.5 5.0	.75 1.9	1.0
WYE !?) Joint	•			
1/C 1/O thru 500 KCN 4KV and 12KV non lea 4KV and 12KV lead	ad (each)	2.0	0.0 .75	0.0

(CODE 12) CONTROL/POWER CABLE, CONNECTIONS, BUS WORK (continued)

WYE (Y) Joint	ט	nit Standar	<u>cis</u>
• •	<u>Install</u>	Remove	<u>Break</u>
1/C Over 500 KCMIL 4KV and 12KV non lead (each) 4KV and 12KV lead (each)	2.0 4.5	0.0 .75	0.0
M/C 1/0 thru 500 KCMIL 4KV and 12KV lead (each)	12.8	1.9	3.7
M/C over 500 KCMIL 4KV and 12KV lead (each)	13.8	1.9	4.0
Prefab Termination		•	
Under 500 KCMIL 4KV and 12KV (each)	1.0	0.0	0.0
Over 500 KCMIL 4KV and 12KV (each)	1.2	0.0	0.0
Elbow Termination	1.0	0.0	0.0
Pothead Under 34.5 KV Single conductor (each) Three conductor (each)	1.5	.75 . 5.6	0.0
		<u>Unit Standa</u> <u>nstall Re</u>	
Switching Table			
M/C		0.0	3.0
Oll Reservoir (transformer oil - 7.5 lbs. per gal.) 3 gal. 10 gal. Over 10 gal.		3.5 7.0 9.0	1.5 3.5 4.5
Epoxy Resin Splice Elt (C 967)		. 50	-
Load Break Cable Tap		. 7	. 2
Elbow Rack-Aluminum	-		
Single phase (C1687) Three phase (C1687)		1.50	.80 1.50

(CODE 12) CONTROL/POWER CABLE, CONNECTIONS, BUS WORK (CONTINUED)

		Unit Sta	indards
Direct Bury Cable		<u>Install</u>	Remove
Trench and backfill (per trench foot)	2	.03	_
Sand and Planking (per trench foot)		.04	_
Hand Dig (per trench foot)		.20	-
Trench, Ground Cable			
Trench and backfill (per trench foot)		.03	-
Hand Dig (per trench foot)		.10	
Miscellaneous			
Alarm. Station Entry	(each)	2.0	1.0
Cable Clamp (C5047)	(each)		. 0
Contactor (for heater/fan)	(each)		. 5
Fan. Exhaust	(each)		. 5
Fan. Vent	(each)		. 5
Heater, 15KW or less	(each)		. 5
Light Fixture, Indoor		1.0	. 5
	(each)		. 2
Safety Switch, Indoor (100A and under)	(each)	2.0	.5
Safety Switch, Indoor (101-400A)			. 5
Safety Switch, Indoor (401-600A) Switch, Micro	(each)		.8
Terminal Block Cabinet	•	2.0 2.0	1.0
Thermostat	(each)		5
	(each)		.5
Toggle Switch	(each)		. 2

...

INFORMATION SHEET (See Page 14 For Unit Values)

COPPER THREADLESS PIPE COPPER NO. 122 HARD DRAWN IN 20-foot Lengths

Standard Pipe Size Inches	Weight Lbs. per Lin. Ft. (Approx.)	Standard Pipe Size Inches	Weight Lbs. per Lin. Ft. (Approx.)
1/4	.376	· 2	1.83
3/8	.483	2 1/2	2.22
1/2	.613	3	3.45
3/4	.780	3 1/2	4.52
1	.989	4	5.72
1 1/4	1.26	5	8.73
1 1/2	1.45	6	12.40

Sizes other than listed can be furnished from Mill stocks.

WEIGHT OF BAR COPPER PER FT.

Width		Thick	ness	
•	1/8"	1/4"	3/8"	1/2"
1/2"	. 247	.485		
1"	. 49	.97		
1 1/2"	. 97	1.445		•
2"		1.94	2.91	3.88
3"		2.91	4.37	5.83
4 "		3.88	5.83	7.77
5"		4 . 85 [.]	7.27	9.70
6"		5.83	8.75	11.66_
e"		7.77	11.66	15.55

To determine weight, use the following Formula for Copper Bus Bar:

Length in ft. X width/12 X thickness/12 X 560 = lbs of copper

WEIGHT OF COPPER ROD PER FT.

Diamete	Ξ.	•	·
1/4		.:378 lbs. cer ft.	3/8"426 lbs. ter ft.
1/2"	-	.75 lbs. per ft.	
5/8"	-	i.18 lbs. per ft.	
3/4"	~	1.7 lbs. per ft.	7/8" - 2.32 lbs. per ft.
. "	-	3.0 lbs. per ft.	
		4.7 lbs. per ft.	
		6.81 lbs. per ft.	

(CODE 14) CONDUIT AND PIPING

<u> </u>	• 1		
Reporting Unit is Per Foot	Unless Otherw	ise Noted	
Conduit, "Rigid" (Above Gr	ound Conduit)		tandards Remove
1/2" to 1" 1 1/4" to 2" 2 1/2" to 3 1/2" 4" to 5" 5 1/2" to 6"			
Conduit. Thinwall. Aluminu Conduit)	m, Flexible, P.	lastic Pipe (Above Ground
2" and Under Over 2"		.10	.04
Note: Units Include Fitti	nes, Supports,	Threading, a	nd Offsets
Conduit/Duct/Trough			•
Concrete Trough - All Size (Average Length 5 to 6 Control Wire Duct Wirewa Cable Pan/Tray (Per Foot Cable Pan Covers (Per Fo	Feet) y (Per Foot))	1.8	.10 .10 .07 .01
Remove and Reset Concrete for Cement Troughs (Per		.20	20
Note: Trenching, Backfill SEE INFORMATION PAGE		Concrete -	
Fire Proof Fittings (EYS Bo	odies)		
2" and under Over 2"		.30 .50	.30
Plastic - Steel (Direct Bus	ry Duct Only)	~	
<pre>1" and under (per foot) 2 1/2" and over (per foot)</pre>	•	.07 .09	.04 .04
Manufactured Bends	i	<u>Unit Star</u> Install	
1" and Under Over 1"	. •	.s 1.0	. 2 . 5
Pull Cunction Boxes - All s	izes		
Jot. Box 10" x 12" Jot. Box (over 12")	(each) (each)	2.0	1.0
Planking			
2" H 10" Treated Plank Units for Cable Pit/Box Ch	(per foot) (ly) (See pg. 1	.05 8 for Sand &	.02 Planking)
Revised 10/86	20		04/09/86

EXCAVATION

(Includes Excavating, Shoring, Backfill, Removing Excess Dirt)
Figured in Number of Trench Feet

Duct	Sections	<u>Install</u>
•	- · ·	F
1 -	4	.08
6 -	•	.10
10 -	_	.15
13 -	- -	.18

Setting Duct in Place (Per Foot)

Duct	<u>Steel</u>	Precast	<u>Plastic</u>
1 - 4	.12	.09	.08
6 - 9	.24	.10	.17
10 - 12	.32	.17	.23
13 - 15	.37	.21	.26

Concrete Encasement of Conduit (Per Trench Foot)

1	_	4	.04
5		9	.06
10	_	12	.08
	_		.10

Example: Three Steel Conduits. Encased in Concrete 10 Feet long.

Trenching	.08	X	10	Feet
Setting	.12	Х	10	Feet
Concrete	.04	X	10	Feet
TOTAL UNITS	. 24			

Miscellaneous ...

(Per 1b.) (See Pg. 22) (each)	. :	.01 .15
(per ft.)	2.0	_
•	3 0	
(per ::.) (eacn)	1.0	. 5
	3.0	1.0
(each)	. 5	. 2
(per fr.)	2.5 .27	.5 .10
	<pre>(each) (per ft.) (per ft.) (each) (each)</pre>	(each) 2.0 (per ft.) 3.0 (per ft.) 3.0 (each) 3.0 (each) 3.0 (each) 3.0 (each) 3.0

(CODE 15) OUTDOOR STRUCTURE

WEIGHT OF STEEL - SEISMIC BRACKETS

·3-

PLATE STEEL

1/4" 4' X 8' = 327# - 10.2# Per Sq. Ft. 3/8" 4' X 8' = 490# - 15.3# Per Sq. Ft. 1/2" 4' X 8' = 653# - 20.4# Per Sq. Ft. 5/8" 4' X 8' = 817# - 25.5# Per Sq. Ft. 3/4" 4' X 8' = 980# - 30.6# Per Sq. Ft. 1" 4' X 8' = 1307# - 40.8# Per Sq. Ft.

TUBE STEEL

2" x 2" X 1/4" - 5.4# Per ft. 3" X 3" X 1/4" - 8.8# Per ft. 4" X 2" X 5/16" - 8.9# Per ft. 4" X 4" X 3/8" - 17.3# Per ft. 5" X 5" X 3/8" - 22.4# Per ft. 6" X 4" X 3/8" - 27.5# Per ft. 5" X 3" X 3/8" - 17.3# Per ft.

BAR STEEL

3" x 1/4" - 2.5# Per Ft. 4" X 1/4" - 3.4# Per Ft. 2" X 1/2" - 3.4# Per Ft. 4" X 1/2" - 6.8# Per Ft.

ANGLE IRON

2" X 2" X 1/4" - 3.2# Per Ft. 2" X 3" X 1/4" - 4.1# Per Ft. 2 1/2" X 2 1/2" X 1/4" - 4.1# Per Ft. 3" X 3" X 1/4" - 4.9# Per Ft.

(CODE 15) CUTDOOR STRUCTURE

Reporting Unit is as Specified

Revised 10/86

ALL BUS AND SWITCH STRUCTURE UNITS - Per Pound

Bus and Switch Structure	* .~	Unit Sta Install	endards Remove
All Structures	(per 15.)*	.01	.01
Static or Lighting Pole (40 ft. min.)	(each)	10.0	10.0

^{*}See Page 24 of Code 15 for Additional Information.

Steel and Structure Distribution Guide (Unit For Steel Only)

S. I. Number	C. Spec	Weight (1bs.)	Unit Stand Install	iards Remove
2226	9871.1	1300	13.0	9.7
332858 332859	9871.2	1300	13.0	9.7
332863	9870.1	2500	25.0	18.7
	9870.2	3500	35.0	26.2
332864 332875	9870.3	3750	37.5	28.1
332975 332995	9870.3	3750	37.5	28.1
332995	9872.1	. 2300	23.0	17.2
	9872.2	3300	33.0	24.7
332333	3012.2		*	
Wood Structure			Unit St	<u>andards</u>
Pole			Install	Remove
25 to 40 ft. (an est 1			2.1
45 to 55 ft. (4.2	2.6
60 to 75 ft. (each)		6.0	3 .5
Ancher (e		•	1.2	. 2
•				. 2
Anchor (Guy) (each)		1.0	. 2
Arm - Cross (each) (inclu arms	ides heavy duty	. 70	. 35
		•	. 70	. 35
Alley (each; mber (each)	4	1.5	. 7
Miscellaneous	mber (eac	•		
	_		. 5	. 25
Dabinet, spare			1.8	.9
Light Fixture,			25	.05
Pipe/Angle Iron			25	. 0 3
Safety Switch.			1.8	. 5
AMPS and unde		(eacn)	1.0	• •
Safety Switch.			3.5	. 5
AMPS-400 AMPS		(each)	3.5	
Safety Swiich, AMPS-600 AMPS		(each)	5.0	. 8

23

04/09/86

MISCELLANEOUS STEEL STRUCTURE WEIGHTS - GUIDE

			Weight
	Structure		(15s.)
		•	
128817	Circuit Switcher High Stand	11'6" Phase Spacing	5,210
	Cittate Switches magnification	Œ 8'0" " "	4,600
138KV	Circuit Switcher Low Stand	11'6" Phase Spacing	4,213
100.0	Usacas Shitemas as stand	8'0" " "	3,784
		•	
138KV	Disc. Switch High Stand	11'6" Phase Spacing	3,000
	Dist. Saiten high brane	8'0" " "	2,702
138KV	Disc. Switch Low Stand	11'6" Phase Spacing	2,500
10024	J134. U41 tell 2011 0 t-11-	8'0" " "	2,278
138KV	Bus Support High Stand	11'6" Phase Spacing	1,603
	han hander i wader a seema	8'0" " "	1.447
138KV	Bus Support Low Stand	11'6" Phase Spacing	1,400
		8'0" " "	1.244
•			
138KV	Single Phase Potential Device St	:: -	965
138KV	Single Phase Inductor Str.		2,585
13574	Three Phase Inductor Str.		8,144
	inter finase inductor of.		
138KV	Wave Trap Support Beam (each)		600
	· ·		
138KV	Dead End Tower	50'-55' Conductor Height	
		70'-75' " "	52.800
		•	
345KV	Disc. Switch High Stand	14'0" Phase Spacing	4.750
	Low Stand	st ts st	3,000
345KV	Bus Support High Stand	14'0" Phase Spacing	3.050
	Low Stand	u u · · · ·	1.730
			1.25
345KV	Single Phase Potential Device St		1,25
345KV	Dead End Tower	50'-55' Conductor Height	41,000
3433.7	Dead End lower	70'-75' " "	56,50
			,
345KV	Cil Circuit Breaker Steel Plate	18" × 18" × 3/4"	7
- 1011	- Cartar Dicares with tract		•
	6" "I" Beam (per foot)		1

(CCDE 17) FOUNDATION AND YARD WORK

SPEC.	<u> </u>		UNITS
C-237		IBT Transf. Foundation	15.0
C-240		138 KV OCB Foundation	135.0
C-241		34.5 KV OCB Foundation 1 0	46.0
C-241		34.5 KV OCB Foundation 3 Ø	48.0
C-242		14.5 KV OCB Foundation	45.0
C-245		14.4 KV Recloser Foundation	45.0
C-247		40 or 60 MVA Trans. Foundation	266.0
C-250		Standard Lighting Foundation	5.0
C-270	Pg. 1	345 Bus Support w/Footing	35.0
C-270	Pg. 1	345 Bus Support w/Cylinders	18.0
C-270	Pg. 2	345 3 Ø Bus Support w/Footing	51.0
C-270	Pg. 2	345 3 Ø Bus Support w/Cylinders	25.0
C-270	Pg. 3	345 3 Ø Bus Support W/Footings	51.0
C-270	Pg. 3	345 3 Ø Bus Support w/ Cylinders	25.0
C-270	Pg. 4	345 Disconnect Fdn. w/Footings	90.0
C-270	Pg. 4	345 Disconnect Fdn. w/Cylinders	40.0
C-270	Pg. 5	345 CCPD Fdn. w/Footings	36.0
C-270	Pg. 5	345 CCPD Fdn. w/Cylinders	20.0
C-275	Pg. 1	138 1 0 Bus Support w/Footings	3 6. 0
C-275	Pg. 1	138 1 0 Bus Support w/Cylinders	20.0
C-275	Pg. 2	138 Structure Fdn. w/Footings	51.0
C-275	Pg. 2	138 Structure Fdn. w/Cylinders	25.0
C-275	Pg. 3	138 Structure Fdn. w/Footings	90.0
C-275	Pg. 3	138 Structure Fdn. w/Cylinders	40.0
C-275	Pg. 4	138 CCVT Structure Fdn. w/Footings	36.0
C-275	Pg. 4	138 CCVT Structure Fdn. w/Cylinders	20.0
C-5302	Pg. 3	Poured Sectionalizer Foundation	45.0
C-5302	Pg: 4	Poured Sectionalizer Foundation	45.0
C-5302	Pg. 6	Poured Sectionalizer Foundation	45.0
C-5302	Pg. 5	Precast Sectionalizer Foundation	16.5
C-5315	₽ġ. :	Outdoor Structure Fdn.	8.0
0-5315	Pg. 2	Metalclad Switchgear Fdn.	57.0
C-5315	Pg. 3	Outdoor Structures & Trans.	42.0
C-5315	Pg. 4	Power Transformer Fdn.	51.0
C-5315	Pg. 5	Steel Pole Foundations	20.0

(CODE 17) FOUNDATION AND YARD WORK (continued)

SPEC. =			<u>עאוד</u>
C-5315	Pg. 6	12.5 KV Recloser Fdn.	23.0
C-5315	Pg. 7	12.5 KV Recloser (Precast) Fdn.	7.0
C-6430	Pg. 1	Pipe Cable Piers - Cylinder	32.0
C-8089	Pg. 1	Trans. Fdns. 100-7500 KVA	42.0
C-8089	Pg. 2	Trans. Fdn. 500-7500 KVA	93.0
C-8201	Pg. 1	34 KV Trans. Fdn. (Precast)	8.0
C-8201	Pg. 2	Metal Clad Switchgear Fdn.	57.0
	Pg. 3	Power Transformers (Poured)	42.0
C-8201	Pg. 5	Recloser Foundation	23.0
C-9874	Pg. Z	Cable Riser Foundation	42.0
•		765 KV Trans. Footing (Per 0)	357.0
		765 EV Trans. Fdn. (Per Ø)	200.0
		765 KV Retaining Wall (Per Q)	250.0
		765 KV Caissons 8' and under	26.0
		765 KV Caissons 8 1/2' to 10'	30.0
		765 KV Caissons Over 10'	33.0
		765 KV Foundations (Fdn. U)	38.0
		765 EV Foundations (Fdn. W)	54.0
		765 KV Circuit Breaker Fdn.	204.0
C-5302	Pg. 5	Sectionalizer Cab. (Precast)	6.4
		Roadway Crossing Trough (25') 334/	84.0
	•	A.B. Chance Screw Anchors	2.0
		Bifurcating Cab. Base	10.0
		12 KV Capacitor (No Piers)	47.0
	<u> </u>		

(CODE 17) FOUNDATION AND YARD WORK (continued)

Reporting Unit is as Specified

-	_	Unit_Standards	
		<u>Install</u>	Remove
Miscellaneous			
Break Concrete	(cubic ft.)	*	.5
Circular Concrete Base	(each)	.8	. 5
Extension Base	(each)	.3	.1
Concrete Slab (EM14920)	(each)	. 5	. 4
Precast Transformer Pad	(each)	1.0	. 5
Spreading Yard Gravel:			
Hand Spread	(per cu. yard)	1.2	-
Machine Spread	(per cu. yard)	.15	-
Loading & Handling Rubble	• •	-	.05

Note: Pea gravel or bank run sand - approx. 3,000 lbs. per cu. yard. Crushed stone, lime #8 - approx. 2,800 lbs. per cu. yard.

e de la companya de	<u>Install</u>	Remove
Foundations		
Sectionalizer Bifurcating Cabinet	7.0 .	1.0
Brick Work		
Install or Remove Brick Work (cubic ft.)	2.0	

(CODE 18) STORAGE BATTERIES AND CHARGING SETS

Reporting Unit is Per Case - See sample below

Storage Battery	Unit_St		
Decrade Dates.	<u>Install</u>		"C" Time
	.3.		
200 AMP Hours or Less	•		
•	<i>i</i> .5	. 3	.7
One to eight cases	12 .3	. 2	.50
Nine to twenty cases		.10	.2
Twenty-one to sixty cases	38 .1	. 10	• 2
Out = 000 !!			
Over 200 Hours			
One to eight cases	1.0	. 8	1.6
Nine to twenty cases	. 8	.50	1.1
Twenty-one to sixty cases	. 5	. 5	. 9
Twenty-one to Sixty cases			•
Battery Charger (each)	7.0	2.5	. 7
Under 12 AMP	4.0	2.0	
12 AMP & over	7.0	3.0	
Battery Rack (each)	3.5	1.5	
Positive or Negative			
Disconnect Cabinet ·	2.5	1.5	

Note:

A O to 200 AMP hour battery has more than one cell to a case.

A battery over 200 AMP hours has one single cell per case.

Samble

Install new battery (less than 200 AMP hours) - 12 cases

First eight cases $8 \times .5 = 4.0$ Remaining four cases $4 \times .3 = 1.2$

Total Units = 5.2


(CODE 19) AUXILIARY EQUIPMENT

Description (Index to Dom Fach Team	Unit Sta	Unit Standards		
Reporting Unit is Per Each Item	<u>Install</u>			
Miscellaneous =		•		
Todinaton Montan	5.0	2.5		
Radiation Monitor	11.0	5.5		
Air Compressor (for station use) Anode (cathodic protection)	2.7	_		
Anode Terminal Box	3.5	1.5		
Anode Test Station	1.3	. 5		
Telephone Equip. and Term. Panel (EM 47105)	9.0	2.0		
Pipe Bond Cabinet	4.3	2.0		
Portable Battery Light	.9	. 5		
Printometer	3.5	1.8		
Rectifier (cathodic) EM 20705	7.0	2.0		
Generator	13.5	4.5		
Generator Control Console (3' x 2' x 4')	18.0	5.0		
Fire Equipment				
Cabinet. External/Wall-Mounted	. 5	-		
House, External/On Concrete Pad	3.5	1.0		
Extinguisher, Wall-Mounted	. 5	. 2		

্রী

(CODE 28) FENCING AND VAULT SLAB

Reporting Unit is as Noted		<u>Unit Sta</u>	
		<u>Install</u>	Remove
Fencing	<u> </u>		
Including Gates and Removab Panels (linear ft.)		. 2	.1
Vault Slab (each)		7.0	7.0
Oil Containment Tub			•
Approx. 12.5' x 7.0' x 6.5' with cover Excavate for Tub	(each)	4.7 18.2	4.7
Great Lakes Liquid Level Con	ntrol Cabinet	3.5	1.0
Miscellaneous			
Sheet Insulation or Barrier	(square ft.)	.10	.03
Pipe Framework	(per linear ft.)	.07	.04
Screen Guard	(per square ft:)	.12	.06



RUSSELL WALD OILLON SURVEYING SERVICES 1M423 SWIFT RD. LONGARD, IL. 50148 PHONE: (630)691-4369 FAX: (630)691-4359 724 SKETCH OF LEASED PARCEL DESISTIFUM

SKOKIE TSS88

Attachment FF-3